

## **APPENDIX A    CONNECTION ASSESSMENT**

# Engineering Study Report

## Joss MPC Wind Aggregated Generating Facility (WAGF)

AESO File No. 1533

Revision: 0

Revision Date: 2016-05-12

|                       | Name                  | Date         | Signature |
|-----------------------|-----------------------|--------------|-----------|
| Prepared by:          | Maz Mazadi, P. Eng.   | May 16, 2016 | Mazadi    |
| Reviewed/Approved by: | Mohamed Kamh, P. Eng. | May 16, 2016 |           |



**APEGA**  
Permit-to-Practice  
P-8200

*Mazadi*  
May 16, 2016

## Executive Summary

### Project Overview

The market participant, Power Renewable Energy Corporation (as the successor to Joss Wind Power Inc.), submitted a system access service request (SASR) to the Alberta Electric System Operator (AESO) for a proposed 120 MW wind aggregated generating facility (WAGF) northeast of the City of Brooks, named the Joss Wind Power Project (the Facility). The Facility includes the market participant's proposed Halsbury 306S substation.

The SASR includes a request for a Rate STS, *Supply Transmission Service*, contract capacity of 120 MW and a Rate DTS, *Demand Transmission Service*, contract capacity of 1 MW for new system access service in the area, and a request for transmission development (collectively, the Project).

The scheduled in-service date (ISD) for the Project is October 2, 2017.

The market participant has indicated that the Facility may in the future be expanded by up to 180 MW for a maximum capability of up to 300 MW. In a separate and subsequent SASR, the market participant has requested a Rate STS contract capacity increase from 120 MW to 300 MW for the system access service to be provided at the proposed Halsbury 306S substation.

This report details the system performance studies undertaken to assess the impact of the Project on the Alberta interconnected electric system (AIES). The impact of the requested Rate STS contract capacity increase to 300 MW is not assessed in this report.

### Existing System

Geographically, the Project is located in the AESO planning area of Empress (Area 48), which is part of the AESO South Planning Region. The Empress area is adjacent to the planning areas of Brooks (Area 47), Medicine Hat (Area 4), Sheerness (Area 43), Vauxhall (Area 52) and Hanna (Area 42).

From a transmission system perspective, the Empress area consists of both 138 kV and 240 kV transmission systems. The Empress area is connected to the planning area of Brooks (Area 47) by the 240 kV transmission lines 951L and 944L (between the Ware Junction 132S and Jenner 275S substations) and to the planning areas of Medicine Hat (Area 4) and Hanna (Area 42) by the 138 kV transmission lines 658L (between the Chappice Lake 649S and Cypress 526S substations) and 7L760/760L (between the Oyen 767S and Amoco Express 163S substations), respectively.

There are a number of existing constraints in the area that are mitigated by remedial action schemes (RASs). Following RAS activation, these constraints are managed in accordance with the procedures set out in Section 302.1 of the ISO rules, *Real Time Transmission Constraint Management* (TCM Rule).

### Study Summary

#### Study Area for the Project

The study area for the project consists of the AESO planning areas of Empress (Area 48), Hanna (Area 42), Sheerness (Area 43), Brooks (Area 47) and Medicine Hat (Area 4). The study area also includes the tie lines connecting these planning areas to neighbouring planning areas. All transmission facilities within the study area were studied and monitored to assess the impact of the Project on the AIES, including any violations of the Reliability Criteria (as defined in Section 2.1.1).

### **Analyses Performed for the Project**

Power flow analysis was performed for the 2017 summer light (SL), 2017 summer peak (SP), and 2017 winter peak (WP) pre- and post-Project scenarios.

Transient stability analysis was performed for the 2017 SL, 2017 SP, and 2017 WP post-Project scenarios.

Short-circuit analysis was performed for the 2017 WP pre-Project scenario and the 2017 WP and 2024 WP post-Project scenarios.

### **Results of the pre-Project studies**

The following is a brief summary of the pre-Project studies results. Results and applicable mitigation measures for selected pre-Project contingencies are shown in greater detail in Table E- 1 below.

#### **Category A (N-0) conditions**

Under Category A conditions, no Reliability Criteria violations were observed for any of the pre-Project scenarios.

#### **Category B (N-1) contingency conditions**

The pre-Project power flow analysis identified a number of system performance issues under Category B contingency conditions, including thermal and voltage criteria violations.

### **Connection alternatives examined for the Project**

This report examined three transmission alternatives to meet the market participant's request for system access service.

#### **Alternative 1 – T-tap connection to the 138 kV transmission system via transmission line 601L**

This alternative involves connecting the Facility to the existing 138 kV transmission line 601L using a T-tap configuration, and includes:

- adding a new 138 kV circuit of approximately 9 km to connect the market participant's proposed Halsbury 306S substation and the 138 kV transmission line 601L using a T-tap configuration; and
- other associated equipment.

#### **Alternative 2 – Radial connection to 138 kV transmission system via Jenner 275S substation**

This alternative involves connecting the Facility to the 138 kV transmission system at the Jenner 275S substation, and includes:

- adding a new 138 kV circuit of approximately 14 km to connect the market participant's proposed Halsbury 306S substation and the Jenner 275S substation;
- adding a 240/138 kV transformer at the Jenner 275S substation;
- expansion of the 138 kV and 240 kV buswork; and
- other associated equipment.

### **Alternative 3 – Radial connection to 240 kV transmission system via Jenner 275S substation**

This alternative involves connecting the Facility to the 240 kV transmission system at the Jenner 275S substation, and includes:

- adding a new 240 kV circuit of approximately 14 km to connect the market participant's proposed Halsbury 306S substation and the Jenner 275S substation;
- adding a 240 kV circuit breaker at the Jenner 275S substation;
- adding a new 240 kV diameter at the Jenner 275S substation; and
- other associated equipment.

### **Connection alternatives not selected for further studies**

Alternative 1 was not selected for further studies because it is not considered technically feasible, given the limited thermal capacity of the existing transmission line 601L and the limited transformation capacity of the existing transformers by which the transmission line 601L is connected to the transmission system. Alternative 2 was not selected for further studies because it involves increased transmission developments and hence, increased costs compared to Alternative 3.

### **Connection alternative selected for further studies**

Alternative 3 was selected for further study as it is technically feasible and has the least amount of transmission development.

### **Results of the post-Project studies**

The following is a brief summary of the post-Project studies results. Results and applicable mitigation measures for selected post-Project contingencies are shown in greater detail in Table E- 1 below.

#### **Category A (N-0) conditions**

Under Category A conditions, no Reliability Criteria violations were observed for any of the post-Project scenarios.

#### **Category B (N-1) contingency conditions**

The post-Project power flow analysis identified a number of system performance issues under Category B contingency conditions, including thermal and voltage criteria violations.

### **Project Interdependencies**

A number of 144 kV transmission lines in the Project area are known to be limited by current transformer (CT). The observed thermal criteria violations on the 144 kV transmission lines 7L159 and 7L16 following the 9L20 contingency can be mitigated by restoring the respective

seasonal continuous thermal ratings of these 144 kV transmission lines (as discussed in Section 7).

The AESO plans to direct the TFO in the Project area to restore the ratings for the 144 kV transmission lines 7L159 and 7L16 to their respective seasonal continuous thermal ratings.

## Conclusions and Recommendation

### Analysis and Conclusions

Table E- 1 provides analysis of, and conclusions about, the impact of the Project for selected contingencies, including mitigations for observed Reliability Criteria violations. The contingencies in Table E- 1 were selected because, in the post-Project scenarios, either new Reliability Criteria violations were observed or Reliability Criteria violations observed in the pre-Project scenarios were materially worsened. Analysis and conclusions, including mitigations, for the full list of studied conditions is provided in Table 8-1 in Section 8 of the report.

**Table E- 1 Project Impact and Mitigation Measures (Selected Contingencies)**

| Condition  | Scenario | Results                                   |                                                                    |                                                                                                  | Mitigation Measures<br>(Pre- and Post-Project)                                                                                                                      |
|------------|----------|-------------------------------------------|--------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            |          | Contingency                               | Pre-Project Observations                                           | Post-Project Comparison                                                                          |                                                                                                                                                                     |
| Category B | 2017 SL  | Loss of 240 kV transmission line 9L29     | No issues on a 240/144 kV transformer at the Nevis 766S substation | New marginal thermal criteria violation on a 240/144 kV transformer at the Nevis 766S substation | <b>Pre:</b> None required for the 240/144 kV transformer at the Nevis 766S substation                                                                               |
|            |          |                                           |                                                                    |                                                                                                  | <b>Post:</b> Can be mitigated by the planned RASs for the Suncor Hand Hills and BluEarth Hand Hills WAGFs (collectively, the planned RASs for the Hand Hills WAGFs) |
|            | 2017 SP  | Loss of 240 kV transmission line 9L29     | No issues on a 240/144 kV transformer at the Nevis 766S substation | New marginal thermal criteria violation on a 240/144 kV transformer at the Nevis 766S substation | <b>Pre:</b> None required for the 240/144 kV transformer at the Nevis 766S substation                                                                               |
|            |          |                                           |                                                                    |                                                                                                  | <b>Post:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs                                                                                          |
|            | 2017 WP  | Loss of the 240 kV transmission line 9L29 | No issues on a 240/144 kV transformer at the Nevis 766S substation | New marginal thermal criteria violation on a 240/144 kV transformer at the Nevis 766S substation | <b>Pre:</b> None required for the 240/144 kV transformer at the Nevis 766S substation                                                                               |
|            |          |                                           |                                                                    |                                                                                                  | <b>Post:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs                                                                                          |
|            |          | Loss of the 240 kV transmission line 9L20 | Thermal criteria violation on the 144 kV transmission line 7L159   | Materially increased loading on transmission line 7L159                                          | <b>Pre:</b> Can be mitigated with completion of line restoration work (Restoration) at transmission line 7L159.                                                     |
|            |          |                                           | No issues on the 144 kV                                            | New material thermal criteria                                                                    | <b>Post:</b> Same as pre-Project                                                                                                                                    |
|            |          |                                           |                                                                    |                                                                                                  | <b>Pre:</b> None required for the 144 kV transmission line 7L16                                                                                                     |

| Condition | Scenario | Results     |                             |                                                         | Mitigation Measures<br>(Pre- and Post-Project)                                 |
|-----------|----------|-------------|-----------------------------|---------------------------------------------------------|--------------------------------------------------------------------------------|
|           |          | Contingency | Pre-Project<br>Observations | Post-Project<br>Comparison                              |                                                                                |
|           |          |             | transmission<br>line 7L16   | violation on the<br>144 kV<br>transmission line<br>7L16 | <b>Post:</b> Can be mitigated with<br>Restoration of transmission line<br>7L16 |

Based on the study results, Alternative 3 is technically viable. The connection assessment identified a number of pre-Project and post-Project system performance issues. Real time operational practices and existing and planned RASs can be used to mitigate most of the pre- and post-Project system performance issues. Mitigation of the observed thermal criteria violations on the 144 kV transmission lines 7L159 and 7L16 following the 9L20 contingency is dependent on the restoration of the 144 kV transmission lines' respective seasonal continuous thermal ratings (as discussed in Section 7 of the report). The AESO plans to direct the TFO in the area to restore the seasonal continuous thermal ratings for transmission lines 7L159 and 7L16.

The Project does not impact the effectiveness of existing RASs in the study area, nor does the Project create the need for new RASs in the study area.

## Recommendation

It is recommended to proceed with the Project using Alternative 3 as the preferred option to respond to the market participant's request for system access service. It also recommended to use real time operational practices and existing and planned RASs to mitigate the identified system performance issues. A minimum rating of 333 MVA is recommended for the new 240 kV circuit and is consistent with good electric industry practice as it would accommodate a possible future expansion of the Facility (for a maximum capability of up to 300 MW). The dependencies identified in this report (i.e., restoration of the seasonal continuous thermal ratings of the 144 kV transmission lines 7L16 and 7L159) need to be in service prior to energization of the Project.

# Contents

|                                                                       |           |
|-----------------------------------------------------------------------|-----------|
| <b>Executive Summary .....</b>                                        | <b>2</b>  |
| <b>1. Introduction .....</b>                                          | <b>10</b> |
| 1.1. Project .....                                                    | 10        |
| 1.1.1. Project Overview.....                                          | 10        |
| 1.1.2. Load Component .....                                           | 10        |
| 1.1.3. Generation Component .....                                     | 10        |
| 1.2. Study Scope .....                                                | 10        |
| 1.2.1. Study Objectives.....                                          | 10        |
| 1.2.2. Study Area .....                                               | 11        |
| 1.2.3. Studies Performed .....                                        | 13        |
| 1.3. Report Overview.....                                             | 13        |
| <b>2. Criteria, System Data, and Study Assumptions.....</b>           | <b>14</b> |
| 2.1. Criteria, Standards, and Requirements .....                      | 14        |
| 2.1.1. AESO Transmission Planning Standards and Criteria .....        | 14        |
| 2.1.2. Information Documents (IDs) and ISO Rules .....                | 15        |
| 2.2. Load and Generation Assumptions .....                            | 15        |
| 2.2.1. Load Assumptions .....                                         | 15        |
| 2.2.2. Generation Assumptions .....                                   | 15        |
| 2.2.3. Intertie Flow Assumptions .....                                | 18        |
| 2.3. System Projects.....                                             | 18        |
| 2.4. Customer Connection Projects.....                                | 18        |
| 2.5. Facility Ratings and Shunt Elements.....                         | 19        |
| 2.6. Dynamic Data and Assumptions .....                               | 21        |
| 2.7. Protection Fault Clearing Times.....                             | 21        |
| 2.8. Voltage Profile Assumptions .....                                | 22        |
| 2.9. HVDC Power Order .....                                           | 23        |
| <b>3. Study Methodology .....</b>                                     | <b>23</b> |
| 3.1. Study Objectives.....                                            | 23        |
| 3.2. Study Scenarios .....                                            | 23        |
| 3.3. Connection Studies Carried Out.....                              | 24        |
| 3.4. Power Flow Analysis .....                                        | 24        |
| 3.4.1. Contingencies Studied.....                                     | 25        |
| 3.5. Short-Circuit Analysis .....                                     | 25        |
| 3.6. Transient Stability Analysis .....                               | 25        |
| <b>4. Pre-Project System Assessment .....</b>                         | <b>25</b> |
| 4.1. Pre-Project Power Flow Results.....                              | 25        |
| 4.1.1. Scenario 1: 2017 SL .....                                      | 25        |
| 4.1.2. Scenario 2: 2017 SP .....                                      | 26        |
| 4.1.3. Scenario 3: 2017 WP.....                                       | 27        |
| <b>5. Connection Alternatives .....</b>                               | <b>28</b> |
| 5.1. Overview.....                                                    | 28        |
| 5.2. Connection Alternatives Examined .....                           | 29        |
| 5.2.1. Connection Alternatives Not Selected for Further Studies ..... | 32        |
| 5.2.2. Connection Alternatives Selected for Further Studies.....      | 33        |
| <b>6. Technical Analysis of the Project Connection .....</b>          | <b>34</b> |
| 6.1. Power Flow Results.....                                          | 34        |
| 6.1.1. Scenario 4: 2017 SL .....                                      | 34        |
| 6.1.2. Scenario 5: 2017 SP .....                                      | 34        |



|                                          |    |
|------------------------------------------|----|
| 6.1.3. Scenario 6: 2017 WP .....         | 35 |
| 6.2. Transient Stability Analysis .....  | 37 |
| 6.3. Short-Circuit Analysis .....        | 37 |
| 6.3.1. Pre-Project .....                 | 37 |
| 6.3.2. Post-Project .....                | 38 |
| 7. Project Interdependencies .....       | 39 |
| 8. Conclusions and Recommendations ..... | 40 |

## Attachments

|              |                                                              |
|--------------|--------------------------------------------------------------|
| Attachment A | 2017 SL Pre-Connection Power Flow Analysis Results           |
| Attachment B | 2017 SL Post-Connection Power Flow Analysis Results          |
| Attachment C | 2017 SP Pre-Connection Power Flow Analysis Results           |
| Attachment D | 2017 SP Post-Connection Power Flow Analysis Results          |
| Attachment E | 2017 WP Pre-Connection Power Flow Analysis Results           |
| Attachment F | 2017 WP Post-Connection Power Flow Analysis Results          |
| Attachment G | 2017 SL Post-Connection Transient Stability Analysis Results |
| Attachment H | 2017 SP Post-Connection Transient Stability Analysis Results |
| Attachment I | 2017 WP Post-Connection Transient Stability Analysis Results |

## Figures

|                                                           |    |
|-----------------------------------------------------------|----|
| Figure 1-1: Transmission system in the Project area ..... | 12 |
| Figure 5-1: Jenner 275S Substation Configuration .....    | 29 |
| Figure 5-2: Alternative 1 .....                           | 30 |
| Figure 5-3: Alternative 2 .....                           | 31 |
| Figure 5-4: Alternative 3 .....                           | 32 |

## Tables

|                                                                                  |    |
|----------------------------------------------------------------------------------|----|
| Table 2-1: Forecast Area Load .....                                              | 15 |
| Table 2-2: Local Non Wind Generators in the Study Cases .....                    | 16 |
| Table 2-3: Existing and Under Construction Wind Generators in Alberta .....      | 16 |
| Table 2-4: Southern and Central Alberta future Wind Projects (Past Gate 2) ..... | 17 |
| Table 2-5: Alberta and WECC System Intertie Flow Assumptions .....               | 18 |
| Table 2-6: Summary of Future System Projects in or near the Study Area .....     | 18 |
| Table 2-7: Summary of Customer Projects in Study Area .....                      | 19 |
| Table 2-8: Summary of Key Transmission Line Ratings .....                        | 19 |
| Table 2-9: Summary of Key Transformer Ratings .....                              | 20 |
| Table 2-10: Summary of Key Shunt Elements in the Study Area .....                | 21 |
| Table 2-11: Generator Dynamic (WT4G2) .....                                      | 21 |
| Table 2-12: Electrical Control Model Dynamic Data (WT4E2) .....                  | 21 |
| Table 2-13: Protection Fault Clearing Times .....                                | 21 |
| Table 2-14: Summary of Voltage at Key Nodes in the Study Area .....              | 22 |
| Table 2-15: HVDC power order .....                                               | 23 |
| Table 3-1: Summary of Study Scenarios .....                                      | 23 |
| Table 3-2: Summary of Studies Performed .....                                    | 24 |
| Table 4-1: 2017 SL (Pre-Project), N-1 Thermal Loading .....                      | 26 |
| Table 4-2: 2017 SP (Pre-Project), N-1 Thermal Loading .....                      | 26 |

**Connection Engineering Study Report**  
**Project 1533 Joss MPC WAGF**

---

|                                                                                  |    |
|----------------------------------------------------------------------------------|----|
| Table 4-3: 2017 SP (Pre-Project), N-1 Voltage Range Violation .....              | 27 |
| Table 4-4: 2017 WP (Pre-Project), N-1 Thermal Loading .....                      | 27 |
| Table 4-5: 2017 WP (Pre-Project), N-1 Voltage Range Violation .....              | 28 |
| Table 6-1: 2017 SL (Post-Project), N-1 Thermal Loading .....                     | 34 |
| Table 6-2: 2017 SP (Post-Project), N-1 Thermal Loading .....                     | 35 |
| Table 6-3: 2017 SP (Post-Project), N-1 Voltage Range Violation .....             | 35 |
| Table 6-4: 2017 WP (Post-Project), N-1 Thermal Loading .....                     | 36 |
| Table 6-5: 2017 WP (Post-Project), N-1 Voltage Range Violation .....             | 36 |
| Table 6-6: Summary of Short-Circuit Current Levels, Pre-Project (2017 WP) .....  | 37 |
| Table 6-7: Summary of Short-Circuit Current Levels, Post-Project (2017 WP) ..... | 38 |
| Table 6-8: Summary of Short-Circuit Current Level, Post-Project (2024 WP) .....  | 39 |
| Table 8-1: Project Impact and Mitigation Measures .....                          | 40 |

# 1. Introduction

This report presents the results of the engineering studies conducted to assess the impact of the Project (as defined below) on the Alberta interconnected electric system (AIES).

## 1.1. Project

### 1.1.1. Project Overview

The market participant, Power Renewable Energy Corporation (as the successor to Joss Wind Power Inc.), submitted a system access service request (SASR) to the Alberta Electric System Operator (AESO) for a proposed 120 MW wind aggregated generating facility (WAGF) northeast of the City of Brooks, named the Joss Wind Power Project (the Facility). The Facility includes the market participant's proposed Halsbury 306S substation.

The SASR includes a request for a Rate STS, *Supply Transmission Service*, contract capacity of 120 MW and a Rate DTS, *Demand Transmission Service*, contract capacity of 1 MW for new system access service in the area, and a request for transmission development (collectively, the Project).

The scheduled in-service date (ISD) for the Project is October 2, 2017.

### 1.1.2. Load Component

- The requested Rate DTS contract capacity is 1 MW

### 1.1.3. Generation Component

- The estimated maximum authorized real power (MARP) of the Facility is 121.9 MW
- The maximum capability (MC) of the Facility is 120 MW
- The Facility includes 53 turbines of 2.3 MW units; Type 4, SWT-2.3 MW-113
- The requested Rate STS contract capacity is 120 MW
- The market participant has indicated that the Facility's MC may increase by an additional 180 MW in a Phase 2 expansion, for a total MC of 300 MW. The expected ISD of the Phase 2 expansion is August 2018. The Phase 2 expansion is the subject of a separate system access service request to the AESO (Project 1698).
- 0.9 power factor (PF) lagging and 0.95 PF leading is assumed at the Facility output as measured at the generator unit terminal, per the technical requirements of Section 502.1 of the ISO Rules, *Wind Aggregated Generation Facilities Technical Requirements*

## 1.2. Study Scope

### 1.2.1. Study Objectives

The objectives of this study are the following:

- Assess the impact of the Project on the performance of the AIES

- Assess any violations of the relevant criteria, standards or requirements of the AESO, both pre- and post-Project.
- Recommend mitigation measures, if required, to enable the reliable connection of the Project to the AIES.

## **1.2.2. Study Area**


### **1.2.2.1. Study Area Description**

Geographically, the Project is located in the AESO planning area of Empress (Area 48), which is part of the AESO South Planning Region. The Empress area is adjacent to the planning areas of Brooks (Area 47), Medicine Hat (Area 4), Sheerness (Area 43), Vauxhall (Area 52) and Hanna (Area 42).

From a transmission system perspective, the Empress area consists of both 138 kV and 240 kV transmission systems. The Empress area is connected to the planning area of Brooks (Area 47) by the 240 kV transmission lines 951L and 944L (between the Ware Junction 132S and Jenner 275S substations) and to the planning areas of Medicine Hat (Area 4) and Hanna (Area 42) by the 138 kV transmission lines 658L (between the Chappice Lake 649S and Cypress 526S substations) and 7L760/760L (between the Oyen 767S and Amoco Express 163S substations), respectively. The transmission system in the Project area is shown in Figure 1-1.

The study area for the project consists of the AESO planning areas of Empress (Area 48), Hanna (Area 42), Sheerness (Area 43), Brooks (Area 47) and Medicine Hat (Area 4). The study area also includes the tie lines connecting these planning areas to neighbouring planning areas. All transmission facilities within the study area were studied and monitored to assess the impact of the Project on the AIES, including any violations of the Reliability Criteria (as defined in Section 2.1.1).

Figure 1-1: Transmission system in the Project area



### 1.2.2.2. Existing Constraints

There are a number of existing constraints in the study area that are mitigated by remedial action schemes (RASs). Following RAS activation, these constraints are managed in accordance with the procedures set out in Section 302.1 of the ISO rules, *Real Time Transmission Constraint Management (TCM Rule)*.

### 1.2.2.3. AESO Long-Term Plans

The *AESO 2015 Long-term Plan* (2015 LTP)<sup>1</sup> includes the following system developments that are in the vicinity of the study area:<sup>2</sup>

- In the near term (to 2020): Rebuild 138 kV line from Cypress substation to Empress substation to higher capacity
- In medium-term (to 2025): Convert Tilley substation from 138/25 kV to 240/138/25 kV substation
- In the medium term: Connect Tilley substation to 240 kV line between Cassils substation near Brooks and Bowmanton substation near Medicine Hat

None of the above developments were modeled in the studies because the ISDs for the developments fall behind the Project ISD.

The Southern Alberta Transmission Reinforcement Project (SATR) is also progressing in southern Alberta. The relevant components of the SATR developments, which are nearby or in the study area, that were modeled in the studies, are listed in Table 2-6.<sup>3</sup>

### 1.2.3. Studies Performed

The following analyses were performed for the pre-Project scenarios:

- Power flow analysis (Category A conditions and B contingencies)
- Short-circuit analysis (Category A conditions)

The following analyses were performed for the post-Project scenarios:

- Power flow analysis (Category A conditions and B contingencies)
- Short-circuit analysis (Category A conditions)
- Transient stability analysis (Category B contingencies)

## 1.3. Report Overview

The Executive Summary provides a high-level summary of the report and its conclusions. Section 1 provides an introduction of the Project. Section 2 describes the criteria, system data, and study assumptions used in this study. Section 3 presents the study methodology used in this study. Section 4 discusses the pre-Project system assessment. Section 5 presents the connection alternatives examined. Section 6 provides a technical analysis of the post-Project system assessment for the alternatives that were selected for further study. Section 7 discusses project interdependencies. Section 8 presents the conclusions and recommendations of this report.

---

<sup>1</sup> The 2015 LTP document is available on the AESO website.

<sup>2</sup> The 2015 LTP identifies the transmission developments in the Vauxhall-Empress-Medicine Hat sub-region on page 34.

<sup>3</sup> The *Southern Alberta Transmission Reinforcement* NID was originally approved by the Alberta Utilities Commission in Decision 2009-126 on September 8, 2009, and issued NID Approval No. U2009-340 on September 17, 2009.

## 2. Criteria, System Data, and Study Assumptions

### 2.1. Criteria, Standards, and Requirements

#### 2.1.1. AESO Transmission Planning Standards and Criteria

The Transmission Planning (TPL) Standards, which are included in the Alberta Reliability Standards, and the AESO's *Transmission Planning Criteria – Basis and Assumptions*<sup>4</sup> (collectively, the Reliability Criteria) were applied to evaluate system performance under Category A system conditions (i.e., all elements in-service) and following Category B contingencies (i.e., single element outage), prior to and following the studied alternative. Below is a summary of Category A and Category B system conditions.

**Category A**, often referred to as the N-0 condition, represents a normal system with no contingencies and all facilities in service. Under this condition, the system must be able to supply all firm load and firm transfers to other areas. All equipment must operate within its applicable rating, voltages must be within their applicable range, and the system must be stable with no cascading outages.

**Category B** events, often referred to as an N-1 or N-G-1 with the most critical generator out of service, result in the loss of any single specified system element under specified fault conditions with normal clearing. These elements are a generator, a transmission circuit, a transformer, or a single pole of a DC transmission line. The acceptable impact on the system is the same as Category A. Planned or controlled interruptions of electric supply to radial customers or some local network customers, connected to or supplied by the faulted element or by the affected area, may occur in certain areas without impacting the overall reliability of the interconnected transmission systems. To prepare for the next contingency, system adjustments are permitted, including curtailments of contracted firm (non-recallable reserved) transmission service electric power transfers.

The TPL standards, TPL-001-AB-0 and TPL-002-AB-0, have referenced Applicable Ratings when specifying the required system performance under Category A and Category B events. For the purpose of applying the TPL standards to the studies documented in this report, Applicable Ratings are defined as follows:

- Seasonal continuous thermal rating of the line's loading limits.
- Highest specified loading limits for transformers.
- For Category A conditions: Voltage range under normal operating condition per AESO Information Document ID #2010-007RS. For the busses not listed in ID #2010-007RS, Table 2-1 in the *Transmission Planning Criteria – Basis and Assumptions* applies.
- For Category B conditions: the extreme voltage range values per Table 2-1 in the *Transmission Planning Criteria – Basis and Assumptions*

---

<sup>4</sup> Filed under a separate cover

## 2.1.2. Information Documents (IDs) and ISO Rules

AESO Information Documents ID #2010-007RS, *General Operating Practices – Voltage Control*, which relates to Section 304.4 of the ISO rules, *Maintaining Network Voltage*, and ID #2013-009R, *South Area Transmission Constraint Management*, which relates to the TCM Rule, were used as guidelines for the studies performed. Pre-contingency operating voltages for key buses within the study area were set in accordance with ID #2010-007RS, if defined in the ID, for all study cases and prior to simulating any contingency events.

### 2.1.2.1. Wind Aggregated Generation Facility (WAGF) Requirements

The Facility connection should meet the technical requirements of Section 502.1 of the ISO rules, *Wind Aggregated Generation Facilities Technical Requirements*.

## 2.2. Load and Generation Assumptions

### 2.2.1. Load Assumptions

The study area load forecast used for this connection study is reflected in Table 2-1 and is at Alberta internal load (AIL) peak, which was based on the *AESO 2012 Long-term Outlook Update* (2012 LTOU). As part of its planning responsibilities, the AESO updates its corporate forecasts routinely to ensure they reflect the latest economic projects, factors and timing. While the AESO has updated its regional forecasts since the connection studies were performed, the use of the current AESO forecast, the *AESO 2016 Long-term Outlook*, would not materially alter the connection study results or affect the conclusions and recommendations in this report.

Table 2-1: Forecast Area Load

| Region Name and Season |              | Forecast Peak Load (MW) |
|------------------------|--------------|-------------------------|
|                        |              | 2017                    |
| Central                | Summer Peak  | 1,642                   |
|                        | Winter Peak  | 1,878                   |
|                        | Summer Light | 1,205                   |
| South                  | Summer Peak  | 2,922                   |
|                        | Winter Peak  | 3,218                   |
|                        | Summer Light | 1,954                   |
| AIL w/o Losses         | Summer Peak  | 11,607                  |
|                        | Winter Peak  | 13,233                  |
|                        | Summer Light | 8,348                   |

### 2.2.2. Generation Assumptions

The existing coal generators and their dispatch levels in and around the study area are listed in Table 2-2.

The forecast wind growth is based on the 2012 LTOU. The existing and under construction wind generators and their dispatch are listed in Table 2-3. The dispatch of future wind projects in the South and Central Region that have passed stage 2 of the AESO Connection Process ahead of Project 1533 is listed in Table 2-4.



**Table 2-2: Local Non Wind Generators in the Study Cases**

| Generator Name | Units | Pmax (MW) | 2017 SL Pgen Net to grid (MW) | 2017 SP Pgen Net to grid (MW) | 2017 WP Pgen Net to grid (MW) |
|----------------|-------|-----------|-------------------------------|-------------------------------|-------------------------------|
| Sheerness      | 1     | 408       | 138                           | 199                           | 311                           |
|                | 2     | 408       | 136                           | 200                           | 329                           |
| Battle River   | 3     | 163       | 87                            | 117                           | 143                           |
|                | 4     | 166       | 88                            | 118                           | 144                           |
|                | 5     | 407       | 262                           | 282                           | 357                           |
| Total          |       | 1,552     | 712                           | 915                           | 1,284                         |

**Table 2-3: Existing and Under Construction Wind Generators in Alberta**

| Plant Name                        | Symbol  | Planning Area | Net to Grid Output (MW) 2017 |
|-----------------------------------|---------|---------------|------------------------------|
| <b>Existing Southern Alberta</b>  |         |               |                              |
| Ardenville Wind                   | ARD1    | 53            | 68                           |
| Blue Trail Wind                   | BTR1    | 53            | 66                           |
| Castle River #1                   | CR1     | 53            | 39                           |
| Castle Rock Wind Farm             | CRR1    | 53            | 77                           |
| Cowley Ridge                      | CRWD    | 53            | 38                           |
| Enmax Taber                       | TAB1    | 52            | 81                           |
| Kettles Hill                      | KHW1    | 53            | 63                           |
| McBride Lake Wind farm            | AKE1    | 53            | 75                           |
| Soderglen Wind                    | GWW1    | 53            | 68                           |
| Summerview 1                      | IEW1    | 53            | 66                           |
| Summerview 2                      | IEW2    | 53            | 66                           |
| Suncor Chin Chute                 | SCR3    | 54            | 30                           |
| Suncor Magrath                    | SCR2    | 53            | 30                           |
| Suncor Wintering Hills            | SCR4    | 43            | 88                           |
| Old Man River                     | OWF1    | 53            | 0*                           |
| Blackspring Ridge                 | BSR1    | 49            | 300                          |
| <b>Subtotal Southern</b>          |         |               | <b>1155</b>                  |
| <b>Existing Central</b>           |         |               |                              |
| Ghost Pine                        | NEP1    | 42            | 82                           |
| Halkirk                           | HAL1    | 42            | 150                          |
| Fortis Bull Creek DG              | BUL1 &2 | 37            | 29.5                         |
| Total                             |         |               | <b>261.5</b>                 |
| <b>Under Construction Central</b> |         |               |                              |
| Total                             |         |               | <b>0</b>                     |
| <b>Subtotal Central</b>           |         |               | <b>261.5</b>                 |

|                      |  |  |               |
|----------------------|--|--|---------------|
| <b>Total Alberta</b> |  |  | <b>1416.5</b> |
|----------------------|--|--|---------------|

\*This wind farm is dispatched to zero to allow for Naturener Wild Rose to be dispatched to full MC such that the total wind generation addition does not change. This dispatch would be more stressful to the study area.

**Table 2-4: Southern and Central Alberta future Wind Projects (Past Gate 2)**

| <b>Southern Wind Project Description</b>      | <b>Proj No</b> | <b>Planned ISD</b> | <b>Planning Area</b> | <b>Pgen (MW)</b> | <b>2017 Dispatch MW</b> |
|-----------------------------------------------|----------------|--------------------|----------------------|------------------|-------------------------|
| Joss MPC WAGF                                 | 1533           | Q3 2017            | 48                   | 120              | 120                     |
| Pteragen Peace Butte 116 MW Wind Farm         | 513            | Q1 2017            | 4                    | 116              | 0                       |
| Naturener Wild Rose Wind Farm                 | 479            | Q3 2017            | 4                    | 204              | 204                     |
| Benign Energy Heritage Wind Farm              | 515            | Q2 2019            | 53                   | 350              | 0                       |
| Enel Alberta Riverview Wind Farm              | 524            | Q4 2017            | 53                   | 115              | 0                       |
| Windy Point Wind Farm                         | 580            | Q1 2017            | 53                   | 61               | 0                       |
| Naturener Wild Rose Wind Farm Phase 2         | 693            | Q4 2016            | 4                    | 200              | 0                       |
| Renewable Energy Services Ltd PC006 Wind Farm | 1500           | Q3 2017            | 53                   | 47               | 0                       |
| Old Elm & Pothole Creek Wind Farm             | 1080           | Q2 2018            | 55                   | 300              | 0                       |
| <b>Subtotal</b>                               |                |                    |                      |                  | <b>324</b>              |
| <b>Central Wind Project Name</b>              | <b>Proj No</b> | <b>Planned ISD</b> | <b>Planning Area</b> | <b>Pgen (MW)</b> | <b>2017 Dispatch MW</b> |
| EON Grizzly Bear Wind Facility                | 1250           | Q4 2017            | 13                   | 120              | 0                       |
| Mainstream Wainwright Wind Project            | 937            | Q1 2018            | 32                   | 90               | 0                       |
| Suncor Hand Hills Wind Energy Project         | 635            | Q4 2018            | 42                   | 80               | 80                      |
| BlueEarth Hand Hills Wind Project             | 678            | Q4 2018            | 42                   | 80               | 80                      |
| <b>Subtotal</b>                               |                |                    |                      |                  | <b>160</b>              |

### 2.2.3. Intertie Flow Assumptions

The following intertie flows between Alberta and WECC system are assumed.

**Table 2-5: Alberta and WECC System Intertie Flow Assumptions**

| Year / Condition | Intertie                     |                                        |                                |                                        |
|------------------|------------------------------|----------------------------------------|--------------------------------|----------------------------------------|
|                  | Import (+) /Export (-) to BC | Import (+) /Export (-) to Saskatchewan | Import (+) /Export (-) to MATL | Import (+) /Export (-) to Medicine Hat |
| 2017 SL          | 0                            | 0                                      | 0                              | 102*                                   |
| 2017 SP          | 530                          | 150                                    | 300                            | -26                                    |
| 2017 WP          | 530                          | 150                                    | 300                            | -26                                    |

For summer peak and winter peak cases, the combined MATL and Alberta-BC intertie flow is considered at 830 MW import (i.e., MATL import at 300 MW and Alberta-BC to be 530 MW). Alberta-SK intertie flow is considered at 150 MW import. Medicine Hat export is 26 MW.

For summer light cases Medicine Hat import is 102 MW.

## 2.3. System Projects

Based on the scheduled ISD for the Project, key system transmission projects near the study area include the SATR developments shown in Table 2-6. These developments were modeled in the study scenarios.

**Table 2-6: Summary of Future System Projects in or near the Study Area**

| Project Name | Project ID | Description                          | In Service Date |
|--------------|------------|--------------------------------------|-----------------|
| SATR         | 787-63     | Rebuild - Stage 2 - 675L/892L        | 2016-05-04      |
|              | 787-6      | Med Hat Area 138 kV Line Development | 2016-12-09      |
|              | 787-64     | New Build - 676L/892L                | 2016-12-09      |

## 2.4. Customer Connection Projects

Customer connection projects within the study area that have passed through Gate 2 of the AESO Connection Process as of May 2016 were modeled within the various study scenarios based on their respective positions in the AESO Connection Queue. Table 2-7 identifies customer connection projects in the study area. It should be noted that the information in this table is subject to change as projects progress.

**Table 2-7: Summary of Customer Projects in Study Area**

| Planning Area | Queue Position* | Project Number | Project Description                               | Planned ISD | Modeled** in the study cases |
|---------------|-----------------|----------------|---------------------------------------------------|-------------|------------------------------|
| 4             | 1               | 513            | Pteragen Peace Butte 116 MW Wind Farm             | Q1-2017     | Yes                          |
| 42            | 6               | 635            | Suncor Hand Hills Wind Energy Project             | Q4-2018     | Yes                          |
| 42            | 7               | 678            | BluEarth Hand Hills Wind Project                  | Q4-2018     | Yes                          |
| 42            | 11              | 863            | TransCanada Keystone KXL Pumpstation #3-Current   | Q3-2016     | Yes                          |
| 42            | 12              | 864            | TransCanada Keystone KXL Pumpstation #4-Armitage  | Q3-2016     | Yes                          |
| 48            | 13              | 865            | TransCanada Keystone KXL Pumpstation #5-Cavendish | Q3-2016     | Yes                          |
| 4             | 2               | 479            | Naturener Wild Rose Wind Farm                     | Q3- 2017    | Yes                          |
| 4             | 8               | 693            | Naturener Wild Rose Wind Farm Phase 2             | Q4-2016     | Yes                          |
| 4             | 45              | 1326           | Medicine Hat - Al Rothbauer 321S Interconnection  | Q2-2017     | No***                        |
| 47            | 62              | 1550           | Fortis Blue Earth Inc./JBS D.G.                   | Q1-2016     | Yes                          |
| 48            | 64              | 1533           | Joss MPC WAGF                                     | Q3-2017     | Yes                          |

\* Per the AESO Connection Queue posted as of May 2016. The projects in the study area, if any, that have queue positions after Project 1533 are not listed in this table and were not modelled in the study cases.

\*\* These projects are dispatched per the load and generation levels set out in Section 2.2. The projects that were not modeled in the study will not affect the results of this connection assessment or the conclusions and recommendations contained in this report.

\*\*\* This connection project was not modeled because the load and generation associated with this connection project is considered in the 2012 LTOU.

## 2.5. Facility Ratings and Shunt Elements

Table 2-8 provides the ratings of the key existing transmission lines in the study area. Table 2-9 provides a summary of the shunt elements modeled in the study area.

**Table 2-8: Summary of Key Transmission Line Ratings**

| Transmission Line Number | From               | To                 | Voltage (kV) | Summer Rating (MVA) | Winter Rating (MVA) |
|--------------------------|--------------------|--------------------|--------------|---------------------|---------------------|
| 9L59                     | Tinchebray 972S    | Anderson 801S      | 240          | 549                 | 701                 |
| 9L950                    | Anderson 801S      | Ware Junction 132S | 240          | 519                 | 663                 |
| 9L934                    | Anderson 801S      | Ware Junction 132S | 240          | 519                 | 663                 |
| 931L                     | Ware Junction 132S | West Brooks 28S    | 240          | 592                 | 665                 |
| 944L                     | Ware Junction 132S | Jenner 275S        | 240          | 550                 | 679                 |
| 951L                     | Ware Junction 132S | Jenner 275S        | 240          | 550                 | 679                 |
| 945L                     | Jenner 275S        | Cypress 562S       | 240          | 550                 | 679                 |
| 1002L                    | Jenner 275S        | Amoco Empress 163S | 240          | 550                 | 679                 |

**Connection Engineering Study Report**  
**Project 1533 Joss MPC WAGF**

| Transmission Line Number | From               | To                   | Voltage (kV) | Summer Rating (MVA) | Winter Rating (MVA) |
|--------------------------|--------------------|----------------------|--------------|---------------------|---------------------|
| 658L                     | Cypress 562S       | Chappice Lake 649S   | 138          | 81                  | 100                 |
| 668L                     | Empress 394S       | Cypress 562S         | 138          | 121                 | 149                 |
| 892L                     | Medicine Hat 41S   | Suffield 895S        | 138          | 67                  | 114                 |
| 100L                     | Suffield 895S      | Tilley 895S          | 138          | 69                  | 115                 |
| 666L                     | Tilley 895S        | West Brooks 28S      | 138          | 98                  | 120                 |
| 7L760                    | Empress Liquid Tap | Oyen 767S            | 144          | 114                 | 145                 |
| 760L                     | Amoco Empress 163S | Empress Liquid Tap   | 138          | 120                 | 148                 |
| 6L09                     | Oyen 767S          | Hanna 763S           | 69           | 23                  | 23                  |
| 7L159                    | Heatburg 948S      | Three Hills 770S     | 144          | 99CT*<br>[114]**    | 99CT<br>[145]       |
| 7L16                     | Nevis 766S         | Heatburg 948S        | 144          | 99CT<br>[114]       | 99CT<br>[145]       |
| 7L85                     | Bull pound 803S    | Anderson 801S        | 144          | 99CT<br>[114]       | 99CT<br>[145]       |
| 7L85                     | Bull pound 803S    | Wintering Hills 804S | 144          | 99CT<br>[114]       | 99CT<br>[145]       |
| 7L128                    | Coyote Lake 963S   | Michichi Creek 802S  | 144          | 99CT<br>[164]       | 99CT<br>[210]       |
| 9L27                     | Cordel 755S        | PaintEarth 863S      | 240          | 332CT               | 332CT               |

\* "CT" indicates that the transmission line is limited by current transformer.

\*\* The values in square brackets represent the transmission lines' ratings if the current transformer limits were removed.

**Table 2-9: Summary of Key Transformer Ratings**

| Substation Name and Number | Transformer ID | Transformer Voltages (kV) | MVA Rating                          |
|----------------------------|----------------|---------------------------|-------------------------------------|
| Cypress 562S               | 562ST1         | 240/144                   | 200                                 |
| Cypress 562S               | 562ST2         | 240/144                   | 200                                 |
| Nevis 766S                 | 901T           | 240/144                   | 100                                 |
| Nevis 766S                 | 701T           | 144/72/25                 | H-M: 33.3<br>X-M: 33.3<br>Y-M: 16.6 |
| Amoco Empress 163S         | 163ST5_A       | 240/144                   | 200                                 |

The details of key shunt elements in the study area are given in Table 2-10.

**Table 2-10: Summary of Key Shunt Elements in the Study Area**

| Substation Name and Number | Nominal Bus Voltage (kV) | Capacitors                      |                                 |                 | Reactors                        |                                 |                             |
|----------------------------|--------------------------|---------------------------------|---------------------------------|-----------------|---------------------------------|---------------------------------|-----------------------------|
|                            |                          | Number of Switched Shunt Blocks | Total at Nominal Voltage (MVar) | Status in Study | Number of Switched Shunt Blocks | Total at Nominal Voltage (MVar) | Status in Study (on or off) |
| Amoco Empress 163S         | 138                      | 2                               | 48.70                           | On              | -                               | -                               | -                           |
| Tilley 498S                | 138                      | 1                               | 27.17                           | On              | -                               | -                               | -                           |
| West Brooks 28S            | 240                      | -                               | -                               | -               | 1                               | -50                             | On                          |
| Lanfine 959S               | 138                      | 2x27.55                         | 55.1                            |                 |                                 |                                 |                             |
|                            | 34.5 (SVC)               | 1x200                           | 200                             | Off/On/TBD      | 1x-100                          | -100                            | Off/On/TBD                  |

## 2.6. Dynamic Data and Assumptions

Type 4 wind machine generic models (WT4G2 and WT4E2) have been used for the Project Transient Stability (Dynamic) analysis. Table 2-11 and Table 2-12 show parameters for these models.

**Table 2-11: Generator Dynamic (WT4G2)**

| Tiqcmd | Tipcmd | VLVPL1 | VLVPL2 | GLVPL | VHVR | CURHVR | Rip_LVPL | T_LVPL |
|--------|--------|--------|--------|-------|------|--------|----------|--------|
| 0.01   | 0.002  | 0.4    | -0.1   | 1.11  | 1.25 | 2.0    | 2.0      | 0.02   |

**Table 2-12: Electrical Control Model Dynamic Data (WT4E2)**

| Tfv    | Kpv  | KIV   | Kpp   | Kip    | Kf     | Tf     | QMX   | QMN   | Ipmax   | Trv     |
|--------|------|-------|-------|--------|--------|--------|-------|-------|---------|---------|
| 0.0    | 15   | 2.0   | 0.08  | 0.01   | 0.0    | 0.08   | 1.0   | -1.2  | 1.1     | 0.0     |
| dPMX   | dPMN | Twpr  | Kqi   | VminCL | VmaxCL | KVi    | Tv    | Tp    | ImaxTD  | Iphl    |
| 0.5    | -0.5 | 0.05  | 0.01  | 0.875  | 1.125  | 55     | 0.05  | 0.05  | 1.115   | 1.25    |
| Iqhl   | Tiqf | FRT_T | FRT_H | FRT_D  | FRT_Iq | MaxFRT | IQMAX | IQMAX | DC Link | VinvMax |
| 1.085  | 0.02 | 0.875 | 0.05  | 0.0    | 2.0    | 1.0    | 1.0   | 1.0   | 1.00    | 1.1     |
| NBR_X  |      |       |       |        |        |        |       |       |         |         |
| 0.1415 |      |       |       |        |        |        |       |       |         |         |

## 2.7. Protection Fault Clearing Times

The list of the contingencies and fault clearing times for existing facilities are listed in Table 2-13.

**Table 2-13: Protection Fault Clearing Times**

| Line | Faulted End | Close End Cycles | Far End Cycles |
|------|-------------|------------------|----------------|
|------|-------------|------------------|----------------|

| Line  | Faulted End                     | Close End Cycles                        | Far End Cycles                              |
|-------|---------------------------------|-----------------------------------------|---------------------------------------------|
| 944L  | Ware Junction 132S<br>(Bus 225) | Ware Junction 132S (Bus225)<br>4 cycles | Jenner 275S (Bus 260)<br>6.5 cycles         |
| 944L  | Jenner 275S (Bus 260)           | Jenner 275S (Bus 260)<br>5.25 cycles    | Ware Junction 132S<br>(Bus 225) 5.75 cycles |
| 945L  | Jenner 275S (Bus 260)           | Jenner 275S (Bus 260)<br>10.5 cycles    | Cypress 562S (Bus 677)<br>5 cycles          |
| 945L  | Cypress 562S<br>(Bus 677)       | Cypress 562S (Bus 677)<br>4 cycles      | Jenner 275S (Bus 260)<br>11.5 cycles        |
| 9L50  | Anderson 801S (Bus<br>1484)     | Anderson 801S (Bus 1484) 5 cycles       | Ware Junction 132S<br>(Bus 225) 6 cycles    |
| 9L50  | Ware Junction 132S<br>(Bus 225) | Ware Junction 132S (Bus225) 5<br>cycles | Anderson 801S (Bus 1484) 6<br>cycles        |
| 1053L | Ware Junction 132S<br>(Bus 225) | Ware Junction 132S (Bus225)<br>5 cycles | Cassils 324S (Bus 918)<br>7 cycles          |
| 1053L | Cassils 324S (Bus 918)          | Cassils 324S (Bus 918) 5 cycles         | Ware Junction 132S<br>(Bus 225) 7 cycles    |

## 2.8. Voltage Profile Assumptions

The AESO Voltage Control Practice ID #2010-007RS is used to establish normal system (i.e., pre-contingency) voltage profiles for key area busses prior to commencing any studies. Table 2-1 of the *Transmission Planning Criteria – Basis and Assumptions* applies for all the busses not included in the ID# 2010-007RS. These voltages will be used to set the voltage profile for the study base cases prior to power flow analysis. The key bus voltages for the study area for the project are shown in Table 2-14.

**Table 2-14: Summary of Voltage at Key Nodes in the Study Area**

| Substation Name and number | Nominal Voltage (kV) | Minimum Operating Limit (kV) | Desired Range (kV) | Maximum Operating Limit (kV) |
|----------------------------|----------------------|------------------------------|--------------------|------------------------------|
| West Brooks 28S            | 138                  | 138                          | 138-144            | 145                          |
| West Brooks 28S            | 240                  | 245                          | 245-260            | 264                          |
| Jenner 2775S               | 240                  | 250                          | 250-260            | 264                          |
| Ware Junction 132S         | 240                  | 250                          | 254-262            | 264                          |
| Amoco Empress 163S         | 240                  | 247                          | 247-260            | 264                          |
| Amoco Empress 163S         | 138                  | 140                          | 140-144            | 145                          |
| Oyen 767S                  | 144                  | 140                          | 143-146            | 155                          |

## 2.9. HVDC Power Order

HVDC power order was determined in accordance with the AESO's planned HVDC operating procedure. The HVDC power order and direction of the flow are shown in Table 2-15.

**Table 2-15: HVDC power order**

| Scenario               | WATL (MW) | EATL (MW) |
|------------------------|-----------|-----------|
| 2017 SL (pre and post) | -         | 400 S→N   |
| 2017 SP (pre and post) | -         | 600 S→N   |
| 2017 WP (pre and post) | -         | 470 S→N   |

## 3. Study Methodology

All the studies were completed using PTI PSS/E version 33.

### 3.1. Study Objectives

The objectives of the study are the following:

- Assess the impact of the Project on the performance of the AIES.
- Identify any violations of the relevant criteria, standard or requirements of the AESO, both pre- and post-Project.
- Recommend mitigation measures, if required, to enable the reliable integration of the Project to the AIES.

### 3.2. Study Scenarios

The scheduled ISD for the Project is October 2, 2017. At the time when the studies for the Project were performed, the scheduled ISD for the Project was August 1, 2017. Hence, the study was conducted for the 2017 summer light (SL), 2017 summer peak (SP), and 2017 winter peak (WP) scenarios. Short-circuit analysis was also completed for the 2024 WP. The shift in the ISD does not materially impact the results of this connection assessment, and does not change the conclusions and recommendations contained in this report.

The study cases were derived from the published AESO Planning Base Case Suite and related auxiliary data files.

Table 3-1 summarizes the study scenarios used for the connection assessment.

**Table 3-1: Summary of Study Scenarios**

| Scenario No.       | Year/Season Load |
|--------------------|------------------|
| Pre-Project System |                  |
| 1                  | 2017 SL          |
| 2                  | 2017 SP          |



|                     |         |
|---------------------|---------|
| 3                   | 2017 WP |
| Post-Project System |         |
| 4                   | 2017 SL |
| 5                   | 2017 SP |
| 6                   | 2017 WP |
| 7                   | 2024 WP |

### 3.3. Connection Studies Carried Out

The following analyses were performed for the pre-Project scenarios:

- Power flow analysis (Category A conditions and B contingencies)
- Short-circuit analysis (Category A conditions)

The following analyses were performed for the post-Project scenarios:

- Power flow analysis (Category A conditions and B contingencies)
- Short-circuit analysis (Category A conditions)
- Transient stability analysis (Category B contingencies)

Table 3-2 summarizes the studies that were carried out for this connection assessment.

**Table 3-2: Summary of Studies Performed**

| Scenario(s) Studied |              | Studies Performed   | System Conditions Studied |
|---------------------|--------------|---------------------|---------------------------|
| Pre-Project         | Post-Project |                     |                           |
| 1, 2, 3             | 4, 5, 6      | Power flow          | Category A and Category B |
| -                   | 4, 5, 6      | Transient stability | Category B                |
| 3                   | 6, 7         | Short-circuit       | Category A                |

### 3.4. Power Flow Analysis

Power flow analysis was performed using PSSE v33 for the pre-Project and post-Project conditions as outlined in Table 3-2.

Pre- and post-Project power flow analysis was performed to identify thermal and voltage criteria violations as per the Reliability Criteria. The purpose of the power flow analysis is to quantify any incremental violations in the study area after the Project is connected.

For the power flow analysis, all transmission facilities in the study area were monitored for thermal and voltage criteria violations under Category A conditions and under Category B contingency conditions.

### **3.4.1. Contingencies Studied**

The study included all Category B contingencies within the study area, including the tie lines connecting the study area to the surrounding planning areas.

## **3.5. Short-Circuit Analysis**

Short-circuit analysis was performed for pre- and post-Project scenarios, as well as for the long-term assessment using the AESO 2024 WP Base Case.

A maximum fault level is provided for the proposed Halsbury 306S substation and neighboring substations with the following assumptions:

- Normal system operation with all transmission elements in service and generation dispatched.
- Three-phase faults and single line to ground fault was simulated.
- Polar coordinates and per unit values was used for reporting the results.

Maximum fault level was provided for the following substations:

- Ware Junction 132S
- Jenner 275S
- Cypress 562S
- Amoco Empress 163S
- Empress 394S
- Wardlow 230S
- Chappice Lake 649S

## **3.6. Transient Stability Analysis**

Transient stability analysis for selected Category B contingencies was performed for the Project using the 2017 study cases. The contingency list and the fault clearing time are shown in Table 2-13. These disturbances cover the major transmission lines in the study area. The active power and angle of the generation units and synchronous motors, bus voltage, branch active and reactive power are monitored for selected buses in the study area.

# **4. Pre-Project System Assessment**

## **4.1. Pre-Project Power Flow Results**

This section provides the results for the pre-Project power flow studies. The analysis of these results, including mitigations for observed Reliability Criteria violations, is provided in in Section 8. All power flows are based on 138 kV system voltage.

### **4.1.1. Scenario 1: 2017 SL**

The pre-Project power flow diagrams are provided in Attachment A.

#### Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

Category B contingency conditions

Thermal criteria violations were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 4-1.

**Table 4-1: 2017 SL (Pre-Project), N-1 Thermal Loading**

| System Condition                               | Overload Branch                                               | 2017 SL Pre-Project |           |
|------------------------------------------------|---------------------------------------------------------------|---------------------|-----------|
|                                                |                                                               | Power Flow (MVA)    | % Loading |
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S) | 7L128 144 kV Line<br>(Coyote Lake 963S - Michichi Creek 802S) | 159.1               | 167.7     |
|                                                | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 120.1               | 126.6     |
|                                                | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 116.8               | 123.09    |
|                                                | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)         | 119.4               | 125.85    |
|                                                | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)  | 125.7               | 132.43    |

#### 4.1.2. Scenario 2: 2017 SP

The pre-Project power flow diagrams are provided in Attachment C.

Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

Category B contingency conditions

Reliability Criteria violations, both thermal and voltage range criteria violations, were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 4-2 and the observed voltage range criteria violations are shown in Table 4-3.

**Table 4-2: 2017 SP (Pre-Project), N-1 Thermal Loading**

| System Condition                                 | Overload Branch                                      | 2017 SP Pre-Project |           |
|--------------------------------------------------|------------------------------------------------------|---------------------|-----------|
|                                                  |                                                      | Power Flow (MVA)    | % Loading |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S)     | 892L 138 kV Line<br>(Suffield 895S – Bowmanton 244S) | 72                  | 107.2     |
| N-1: 669L<br>(Amoco Empress 163S - Cypress 562S) | 668L 138 kV Line<br>(Empress 394S - Cypress 562S)    | 121.4               | 100.4     |

|                                                 |                                                               |       |       |
|-------------------------------------------------|---------------------------------------------------------------|-------|-------|
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S ) | 7L128 144 kV Line<br>(Coyote Lake 963S - Michichi Creek 802S) | 160.8 | 169.4 |
|                                                 | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 121.8 | 128.3 |
|                                                 | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 117.9 | 124.2 |
|                                                 | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)         | 111.7 | 117.7 |
|                                                 | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)  | 121.9 | 128.5 |

**Table 4-3: 2017 SP (Pre-Project), N-1 Voltage Range Violation**

| System Condition                             | Bus No., substation, voltage(kV) | 2017 SP Pre-Project |                              |                       |
|----------------------------------------------|----------------------------------|---------------------|------------------------------|-----------------------|
|                                              |                                  | Initial Voltage p.u | Post contingency Voltage p.u | Range                 |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S) | 275 Tilley 498S 138 kV           | 1.01                | 0.88                         | Below extreme minimum |

#### 4.1.3. Scenario 3: 2017 WP

The pre-Project power flow diagrams are provided in Attachment E.

##### Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

##### Category B contingency conditions

Reliability Criteria violations, both thermal and voltage range criteria violations, were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 4-4 and the observed voltage range criteria violations are shown in Table 4-5.

**Table 4-4: 2017 WP (Pre-Project), N-1 Thermal Loading**

| System Condition                               | Overload Branch                                 | 2017 WP Pre-Project |           |
|------------------------------------------------|-------------------------------------------------|---------------------|-----------|
|                                                |                                                 | Power Flow (MVA)    | % Loading |
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S) | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S) | 123.9               | 130.5     |

|                                         |                                                               |       |       |
|-----------------------------------------|---------------------------------------------------------------|-------|-------|
|                                         | 7L128 144 kV Line<br>(Coyote Lake 963S - Michichi Creek 802S) | 157   | 165.4 |
|                                         | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 118.7 | 125.1 |
|                                         | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)         | 102.7 | 108.2 |
|                                         | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)  | 109.4 | 115.3 |
| N-1: 9L20<br>(Nevis 766S – Cordel 755S) | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 95.7  | 100.9 |

**Table 4-5: 2017 WP (Pre-Project), N-1 Voltage Range Violation**

| System Condition                             | Bus No., substation, voltage(kV) | 2017 WP Pre-Project |                         |                       |
|----------------------------------------------|----------------------------------|---------------------|-------------------------|-----------------------|
|                                              |                                  | Initial Voltage p.u | Post outage Voltage p.u | Range                 |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S) | 270 Suffield 895S 138 kV         | 1.0                 | 0.81                    | Below extreme minimum |
|                                              | 275 Tilley 498S 138 kV           | 1.01                | 0.77                    | Below extreme minimum |


## 5. Connection Alternatives

### 5.1. Overview

Three transmission alternatives were examined to meet the market participant's request for system access service. The transmission alternatives that were examined involve developments in the vicinity of the existing Jenner 275S and Wardlow 230S substations, which are located in the Project area.

As shown in Figure 5-1, the Jenner 275S substation contains two 240/25 kV 50/67/83 MVA transformers (T1 and T2). Transformer T1 is also connected to a step up 138/25 kV 15/20/25 MVA transformer (T3), which feeds the Wardlow 230S substation via the 138 kV transmission line 601L.

**Figure 5-1: Jenner 275S Substation Configuration**



## 5.2. Connection Alternatives Examined

Below is a description of the developments associated with the transmission alternatives that were examined for the Project.

### Alternative 1 – T-tap connection to the 138 kV transmission system via transmission line 601L


Alternative 1 involves connecting the Facility to the 138 kV transmission line 601L using a T-tap configuration, as shown in Figure 5-2.

This alternative includes:

- adding a new 138 kV circuit of approximately 9 km to connect the market participant's proposed Halsbury 306S substation and the existing 138 kV transmission line 601L using a T-tap configuration; and
- other associated equipment.



Figure 5-3: Alternative 2



### Alternative 3 – Radial connection to 240 kV transmission system via Jenner 275S substation

Alternative 3 involves connecting the Facility to the 240 kV transmission system at the Jenner 275S substation, as shown in Figure 5-4.


This alternative includes:

- adding a new 240 kV circuit of approximately 14 km to connect the market participant's proposed Halsbury 306S substation and the Jenner 275S substation;
- adding a 240 kV circuit breaker at the Jenner 275S substation;
- adding a new 240 kV diameter at the Jenner 275S substation;<sup>6</sup> and
- other associated equipment.

<sup>6</sup> The TFO has advised that a new 240 kV diameter would be required at the Jenner 275S substation to connect the new 240 kV transmission circuit.



Figure 5-4: Alternative 3



### 5.2.1. Connection Alternatives Not Selected for Further Studies

#### Alternative 1

Alternative 1 is not considered to be technically feasible, given the limited thermal capacity of the existing transmission line 601L and the limited transformation capacity of the existing transformers T1 and T3 by which the transmission line 601L is connected to the transmission system. Alternative 1 was not selected for further study.

#### Alternative 2

Alternative 2 is considered technically feasible. Alternative 2 involves increased transmission developments and hence, increased costs compared to Alternative 3. Alternative 2 was not selected for further study.

### **5.2.2. Connection Alternatives Selected for Further Studies**

Alternative 3 was selected for further study as it is technically feasible and has the least amount of transmission development.

## 6. Technical Analysis of the Project Connection

### 6.1. Power Flow Results

This section provides the results for the post-Project power flow studies. The analysis of these results, including mitigations for observed Reliability Criteria violations, is provided in in Section 8. All power flows are based on 138 kV system voltage.

#### 6.1.1. Scenario 4: 2017 SL

The 2017 SL post-Project power flow diagrams are provided in Attachment B.

##### Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

##### Category B contingency conditions

Thermal criteria violations were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 6-1.

**Table 6-1: 2017 SL (Post-Project), N-1 Thermal Loading**

| System Condition                                | Overload Branch                                               | 2017 SL Pre-Project |           | 2017 SL Post-Project |           | %Diff |
|-------------------------------------------------|---------------------------------------------------------------|---------------------|-----------|----------------------|-----------|-------|
|                                                 |                                                               | Power Flow (MVA)    | % Loading | Power Flow (MVA)     | % Loading |       |
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S ) | 7L128 144 kV Line<br>(Coyote Lake 963S - Michichi Creek 802S) | 159.1               | 167.7     | 160.5                | 169.2     | 1.5   |
|                                                 | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 120.1               | 126.6     | 122.9                | 129.5     | 2.9   |
|                                                 | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 116.8               | 123.1     | 119.5                | 126       | 2.9   |
|                                                 | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)         | 119.4               | 125.9     | 117                  | 123.2     | -2.7  |
|                                                 | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)  | 125.7               | 132.4     | 123.2                | 129.8     | -2.6  |
|                                                 | Nevis Transformer 766S901T 240/144 kV                         | 100                 | 100       | 103.2                | 103.2     | 3.2   |

#### 6.1.2. Scenario 5: 2017 SP

The 2017 SP post-Project Power flow diagrams are provided in Attachment D.

##### Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

##### Category B contingency conditions

Reliability Criteria violations, both thermal and voltage range criteria violations, were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 6-2 and the observed voltage range criteria violations are shown in Table 6-3.

**Table 6-2: 2017 SP (Post-Project), N-1 Thermal Loading**

| System Condition                                | Overload Branch                                                | 2017 SP Pre-Project |           | 2017 SP Post-Project |           | %diff |
|-------------------------------------------------|----------------------------------------------------------------|---------------------|-----------|----------------------|-----------|-------|
|                                                 |                                                                | Power Flow (MVA)    | % Loading | Power Flow (MVA)     | % Loading |       |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S)    | 892L 138 kV Line<br>(Suffield 895S – Bowmanton 244S)           | 72                  | 107.2     | 72.2                 | 107.7     | 0.5   |
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S ) | 7L128 144 kV Line<br>(Coyote Lake 963S to Michichi Creek 802S) | 160.8               | 169.4     | 160.8                | 169.4     | 0     |
|                                                 | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)                | 121.8               | 128.3     | 124.4                | 131.1     | 2.8   |
|                                                 | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)               | 117.9               | 124.2     | 120.5                | 127.0     | 2.8   |
|                                                 | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)          | 111.7               | 117.7     | 108.8                | 114.6     | -3.1  |
|                                                 | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)   | 121.9               | 128.5     | 118.9                | 125.3     | -3.2  |
|                                                 | Nevis Transformer 766S901T 240/144 kV                          | 98.4                | 98.4      | 101.3                | 101.3     | 2.9   |

**Table 6-3: 2017 SP (Post-Project), N-1 Voltage Range Violation**

| System Condition                             | Bus No., substation, voltage (kV) | 2017 SP Pre-Project |                         |                       | 2017 SP Post-Project |                         |                       |
|----------------------------------------------|-----------------------------------|---------------------|-------------------------|-----------------------|----------------------|-------------------------|-----------------------|
|                                              |                                   | Initial Voltage p.u | Post outage Voltage p.u | Range                 | Initial Voltage p.u  | Post outage Voltage p.u | Range                 |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S) | 275 Tilley 498S 138 kV            | 1.01                | 0.88                    | Below extreme minimum | 1.00                 | 0.88                    | Below extreme minimum |

### 6.1.3. Scenario 6: 2017 WP

The 2017 WP post-Project power flow diagrams are provided in Attachment F.

#### Category A conditions

No Reliability Criteria violations were observed under Category A conditions.

### Category B contingency conditions

Reliability Criteria violations, both thermal and voltage range criteria violations, were observed under Category B contingency conditions.

The observed thermal criteria violations are shown in Table 6-4 and the observed voltage range criteria violations are shown in Table 6-5.

**Table 6-4: 2017 WP (Post-Project), N-1 Thermal Loading**

| System Condition                                | Overload Branch                                               | 2017 WP Pre-Project |           | 2017 WP Post-Project |           | %Diff |
|-------------------------------------------------|---------------------------------------------------------------|---------------------|-----------|----------------------|-----------|-------|
|                                                 |                                                               | Power Flow (MVA)    | % Loading | Power Flow (MVA)     | % Loading |       |
| N-1: 9L20<br>(Nevis 766S – Cordel 755S)         | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 95.7                | 100.9     | 102.3                | 107.8     | 6.9   |
|                                                 | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 90.5                | 95.3      | 97                   | 102.2     | 6.9   |
| N-1: 9L29<br>(Oakland 946S - Coyote Lake 963S ) | 7L159 144 kV Line<br>(7L16 Tap - Heatburg 948S)               | 123.9               | 130.5     | 126.6                | 133.4     | 2.9   |
|                                                 | 7L128 144 kV Line<br>(Coyote Lake 963S - Michichi Creek 802S) | 157                 | 165.4     | 157                  | 165.4     | 0     |
|                                                 | 7L16 144 kV Line<br>(Nevis 766S – Heatburg 948S)              | 118.7               | 125.1     | 121.4                | 127.9     | 2.8   |
|                                                 | 7L85 144 kV Line<br>(Bull Pound 803S – Anderson 801S)         | 102.7               | 108.2     | 100                  | 105.3     | -2.9  |
|                                                 | 7L85 144 kV Line<br>(Wintering Hills 804S – Bull Pound 803S)  | 109.4               | 115.3     | 106.8                | 112.5     | -2.8  |
|                                                 | Nevis Transformer 766S901T<br>240/144 kV                      | 98.3                | 98.3      | 101.3                | 101.3     | 3     |

**Table 6-5: 2017 WP (Post-Project), N-1 Voltage Range Violation**

| System Condition                             | Bus No., substation, voltage (kV) | 2017 WP Pre-Project |                         |                       | 2017 WP Post-Project |                         |                       |
|----------------------------------------------|-----------------------------------|---------------------|-------------------------|-----------------------|----------------------|-------------------------|-----------------------|
|                                              |                                   | Initial Voltage p.u | Post outage Voltage p.u | Range                 | Initial Voltage p.u  | Post outage Voltage p.u | Range                 |
| N-1: 666L<br>(Tilley 498S – West Brooks 28S) | 270 Suffield 895S 138 kV          | 1.0                 | 0.81                    | Below extreme minimum | 1.00                 | 0.8                     | Below extreme minimum |
|                                              | 275 Tilley 498S 138 kV            | 1.01                | 0.77                    | Below extreme minimum | 1.01                 | 0.77                    | Below extreme minimum |

## 6.2. Transient Stability Analysis

The transient stability analysis was performed on the 2017 SL, 2017 SP and 2017 WP scenarios for the selected alternative. Bus voltages, generators' active power and angle, synchronous motors active power and angle, branch active and reactive power were monitored for the contingencies listed in Table 2-13.

The results did not indicate any transient stability concerns, and the system showed acceptable dynamic response to all studied Category B contingencies. Detailed stability plots are provided in Attachments G to I, respectively.

## 6.3. Short-Circuit Analysis

Short circuit analysis was performed using the 2017 WP and 2024 WP scenarios to determine the expected system short circuit levels<sup>7</sup> in the vicinity of the proposed Halsbury 306S substation. Single phase and three phase fault currents were calculated at the proposed Halsbury 306S substation as well as the adjacent existing substations. The results are provided in the subsections below for consideration in the Project facility design.

### 6.3.1. Pre-Project

Table 6-6 provides the 2017 WP short-circuit levels before the Project.

**Table 6-6: Summary of Short-Circuit Current Levels, Pre-Project (2017 WP)**

| Substation         | Base Voltage (kV) | Pre-fault Voltage (p.u.) | 3-phase                              |              | Single-phase-to-ground           |              |
|--------------------|-------------------|--------------------------|--------------------------------------|--------------|----------------------------------|--------------|
|                    |                   |                          | Positive Sequence Impedance (p.u.) 1 | Current (kA) | Zero Sequence Impedance (p.u.) 1 | Current (kA) |
| Ware Junction 132S | 240               | 1.055                    | 0.003434+j0.019174                   | 13.59        | 0.002765+j0.019272               | 13.40        |
| Jenner 275S        | 240               | 1.063                    | 0.006036+j0.034269                   | 7.61         | 0.025321+j0.111509               | 4.32         |
|                    | 138               | 1.023                    | 0.078275+j0.840580                   | 0.525        | 0.050727+j1.448889               | 0.424        |
| Cypress            | 240               | 1.07                     | 0.006486+j0.043672                   | 5.99         | 0.015888+j0.111009               | 3.98         |

<sup>7</sup> Short-circuit current studies were based on modeling information provided to the AESO by third parties. The authenticity of the modeling information has not been validated. Fault levels could change as a result of system developments, new customer connections, or additional generation in the area. It is recommended that these changes be monitored and fault levels reviewed to ensure that the fault levels are within equipment operating limits. The information provided in this study should not be used as the sole source of information for electrical equipment specifications or for the design of safety-grounding systems.

|                    |     |       |                    |       |                    |      |
|--------------------|-----|-------|--------------------|-------|--------------------|------|
| 562S               | 138 | 1.017 | 0.005992+j0.048781 | 8.89  | 0.011986+j0.090791 | 6.99 |
| Amoco Empress 163S | 240 | 1.069 | 0.006362+j0.043321 | 6.04  | 0.017878+j0.116070 | 3.89 |
|                    | 138 | 1.016 | 0.006399+j0.048942 | 8.84  | 0.015785+j0.101385 | 6.58 |
| Empress 394S       | 138 | 1.016 | 0.006705+j0.049613 | 8.72  | 0.015449+j0.100869 | 6.56 |
| Wardlow 230S       | 138 | 1.022 | 0.110085+j0.902412 | 0.487 | 0.115679+j1.678937 | 0.38 |
| Chappice Lake 649S | 138 | 1.016 | 0.055496+j0.114199 | 3.47  | 0.100094+j0.332869 | 2.21 |

**Note:** 1) per unit (p.u.) quantities are on 100 MVA base and system voltage base.

### 6.3.2. Post-Project

Table 6-7 and Table 6-8 provide the 2017 WP and 2024 WP short-circuit levels after the Project.

**Table 6-7: Summary of Short-Circuit Current Levels, Post-Project (2017 WP)**

| Substation         | Base Voltage (kV) | Pre-fault Voltage (p.u.) | 3-phase                              |              | Single-phase-to-ground           |              |
|--------------------|-------------------|--------------------------|--------------------------------------|--------------|----------------------------------|--------------|
|                    |                   |                          | Positive Sequence Impedance (p.u.) 1 | Current (kA) | Zero Sequence Impedance (p.u.) 1 | Current (kA) |
| Ware Junction 132S | 240               | 1.062                    | 0.003377+j0.018991                   | 13.8         | 0.002705+j0.018597               | 13.7         |
| Jenner 275S        | 240               | 1.072                    | 0.005629+j0.033089                   | 7.96         | 0.012114+j0.068444               | 5.86         |
|                    | 138               | 1.032                    | 0.076944+j0.840065                   | 0.531        | 0.037587+j1.406107               | 0.434        |
| Cypress 562S       | 240               | 1.079                    | 0.006274+j0.042981                   | 6.15         | 0.014503+j0.099902               | 4.29         |
|                    | 138               | 1.021                    | 0.005767+j0.047904                   | 9.09         | 0.010862+j0.082717               | 7.40         |
| Amoco Empress 163S | 240               | 1.078                    | 0.006147+j0.042614                   | 6.20         | 0.016461+j0.104952               | 4.18         |
|                    | 138               | 1.02                     | 0.006190+j0.048120                   | 9.04         | 0.014491+j0.093000               | 6.96         |
| Empress 394S       | 138               | 1.02                     | 0.006493+j0.048780                   | 8.91         | 0.014190+j0.092544               | 6.93         |
| Wardlow 230S       | 138               | 1.031                    | 0.108713+j0.901961                   | 0.492        | 0.102484+j1.636072               | 0.388        |
| Chappice Lake 649S | 138               | 1.02                     | 0.055367+j0.113867                   | 3.49         | 0.099700+j0.330047               | 2.23         |

|                  |     |       |                    |      |                    |      |
|------------------|-----|-------|--------------------|------|--------------------|------|
| Halsbury<br>306S | 240 | 1.072 | 0.008201+j0.052935 | 4.99 | 0.006512+j0.068304 | 4.56 |
|------------------|-----|-------|--------------------|------|--------------------|------|

**Note:** 1) per unit (p.u.) quantities are on 100 MVA base and system voltage base.

**Table 6-8: Summary of Short-Circuit Current Level, Post-Project (2024 WP)**

| Substation         | Base Voltage (kV) | Pre-fault Voltage (p.u.) | 3-phase                              |              | Single-phase-to-ground           |              |
|--------------------|-------------------|--------------------------|--------------------------------------|--------------|----------------------------------|--------------|
|                    |                   |                          | Positive Sequence Impedance (p.u.) 1 | Current (kA) | Zero Sequence Impedance (p.u.) 1 | Current (kA) |
| Ware Junction 132S | 240               | 1.063                    | 0.003351+j0.018217                   | 13.81        | 0.005031+j0.022102               | 12.73        |
| Jenner 275S        | 240               | 1.057                    | 0.006103+j0.031997                   | 7.81         | 0.011910+j0.060583               | 6.01         |
|                    | 138               | 1.015                    | 0.074837+j0.793943                   | 0.532        | 0.036461+j1.336838               | 0.435        |
| Cypress 562S       | 240               | 1.052                    | 0.007680+j0.041225                   | 6.03         | 0.003905+j0.034699               | 6.45         |
|                    | 138               | 1.021                    | 0.009030+j0.047898                   | 8.76         | 0.004725+j0.053001               | 8.64         |
| Amoco Empress 163S | 240               | 1.051                    | 0.007503+j0.040880                   | 6.08         | 0.006051+j0.042789               | 6.05         |
|                    | 138               | 1.021                    | 0.009197+j0.048144                   | 8.72         | 0.007366+j0.060132               | 8.21         |
| Empress 394S       | 138               | 1.021                    | 0.009522+j0.048870                   | 8.58         | 0.007404+j0.060841               | 8.10         |
| Wardlow 230S       | 138               | 1.013                    | 0.106293+j0.855624                   | 0.492        | 0.101314+j1.566655               | 0.386        |
| Chappice Lake 649S | 138               | 1.015                    | 0.050951+j0.117012                   | 3.33         | 0.104575+j0.428414               | 1.84         |
| Halsbury 306S      | 240               | 1.057                    | 0.008657+j0.051905                   | 4.83         | 0.006962+j0.065289               | 4.47         |

**Note:** 1) per unit (p.u.) quantities are on 100 MVA base and system voltage base.

## 7. Project Interdependencies

The Project is not dependent on the completion of any 2015 LTP system transmission developments in order to proceed.

A number of 144 kV transmission lines in the Project area are known to be limited by current transformer (CT), as shown in Table 2-8.



Restoration of the seasonal continuous thermal ratings of the 144 kV transmission lines 7L159 and 7L16 can mitigate the thermal criteria violations that are observed following the contingencies of the 240 kV transmission line 9L20.

The AESO plans to direct the TFO in the Project area to restore the ratings for the transmission lines 7L159 and 7L16 to their respective seasonal continuous thermal ratings. The restoration of these transmission lines' respective seasonal continuous thermal ratings is outside the scope of the Project.

## 8. Conclusions and Recommendations

### Analysis and Conclusions

Table 8-1 provides analysis of, and conclusions about, the impact of the Project, including mitigations for observed Reliability Criteria violations.

**Table 8-1: Project Impact and Mitigation Measures**

| Condition  | Scenario | Results                               |                                                                  |                         | Mitigation Measures<br>(Pre- and Post-Project)                                                                                                                                                         |
|------------|----------|---------------------------------------|------------------------------------------------------------------|-------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            |          | Contingency                           | Pre-Project Observations                                         | Post-Project Comparison |                                                                                                                                                                                                        |
| Category A | 2017 SL  | Not applicable                        | No issues                                                        | No impact               | None required                                                                                                                                                                                          |
|            | 2017 SP  | Not applicable                        | No issues                                                        | No impact               | None required                                                                                                                                                                                          |
|            | 2017 WP  | Not applicable                        | No issues                                                        | No impact               | None required                                                                                                                                                                                          |
| Category B | 2017 SL  | Loss of 240 kV transmission line 9L29 | Thermal criteria violation on the 144 kV transmission line 7L128 | No material change      | <b>Pre:</b> Can be mitigated by the planned RASs for the Suncor Hand Hills and BluEarth Hand Hills WAGFs (collectively, the planned RASs for the Hand Hills WAGFs)<br><b>Post:</b> Same as pre-Project |
|            |          |                                       | Thermal criteria violation on the 144 kV transmission line 7L159 | No material change      | <b>Pre:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs<br><b>Post:</b> Same as pre-Project                                                                                          |
|            |          |                                       | Thermal criteria violation on the 144 kV transmission line 7L16  | No material change      | <b>Pre:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs<br><b>Post:</b> Same as pre-Project                                                                                          |
|            |          |                                       | Thermal criteria violation on the 144 kV transmission line 7L85  | No material change      | <b>Pre:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs.<br><b>Post:</b> Same as pre-Project                                                                                         |
|            |          |                                       |                                                                  |                         |                                                                                                                                                                                                        |
|            |          |                                       |                                                                  |                         |                                                                                                                                                                                                        |
|            |          |                                       |                                                                  |                         |                                                                                                                                                                                                        |
|            |          |                                       |                                                                  |                         |                                                                                                                                                                                                        |

Connection Engineering Study Report  
Project 1533 Joss MPC WAGF

| Condition | Scenario | Results                                   |                                                                                  |                                                                                                  | Mitigation Measures<br>(Pre- and Post-Project)                                                       |
|-----------|----------|-------------------------------------------|----------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|
|           |          | Contingency                               | Pre-Project<br>Observations                                                      | Post-Project<br>Comparison                                                                       |                                                                                                      |
|           |          |                                           | No issues                                                                        | New marginal thermal criteria violation on a 240/144 kV transformer at the Nevis 766S substation | <b>Pre:</b> None required                                                                            |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Post:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs                           |
|           | 2017 SP  | Loss of the 138 kV transmission line 666L | Thermal criteria violation on the 138 kV transmission line 892L                  | No material change                                                                               | <b>Pre:</b> Currently being managed by using real time operational practices                         |
|           |          |                                           | Voltage range criteria violation on the 138 kV bus at the Tilley 498S substation | No change                                                                                        | <b>Post:</b> Can also be managed by using real time operational practices                            |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Pre:</b> Currently being mitigated by using a RAS at Tilley 498S substation (the Tilley 498S RAS) |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Post:</b> Can continue to be mitigated using the Tilley 498S RAS                                  |
|           |          | Loss of the 138 kV transmission line 669L | Marginal thermal criteria violation on the 138 kV transmission line 668L         | Thermal loading reduced (no longer a Reliability Criteria violation)                             | <b>Pre:</b> Currently being managed by using real time operational practices                         |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Post:</b> None required                                                                           |
|           |          | Loss of 240 kV transmission line 9L29     | Thermal criteria violation on the 144 kV transmission line 7L128                 | No material change                                                                               | <b>Pre:</b> be mitigated by the planned RASs for the Hand Hills WAGFs                                |
|           |          |                                           | Thermal criteria violation on the 144 kV transmission line 7L159                 | No material change                                                                               | <b>Post:</b> Same as pre-Project                                                                     |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Pre:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs                            |
|           |          |                                           | Thermal criteria violation on the 144 kV transmission line 7L16                  | No material change                                                                               | <b>Post:</b> Same as pre-Project                                                                     |
|           |          |                                           |                                                                                  |                                                                                                  | <b>Pre:</b> Can be mitigated by the planned RASs for the Hand Hills WAGFs                            |
|           |          |                                           | Thermal criteria                                                                 | No material change                                                                               | <b>Post:</b> Same as pre-Project                                                                     |

Connection Engineering Study Report  
Project 1533 Joss MPC WAGF

| Condition | Scenario | Results                                            |                                                                                 |                                                                                                                          | Mitigation Measures<br>(Pre- and Post-Project)                                |
|-----------|----------|----------------------------------------------------|---------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------|
|           |          | Contingency                                        | Pre-Project<br>Observations                                                     | Post-Project<br>Comparison                                                                                               |                                                                               |
|           |          |                                                    | violation on the<br>144 kV<br>transmission<br>line 7L85                         |                                                                                                                          | <b>Post:</b> Same as pre-Project                                              |
|           |          |                                                    | No issues                                                                       | New marginal<br>thermal<br>criteria<br>violation on a<br>240/144 kV<br>transformer at<br>the Nevis<br>766S<br>substation | <b>Pre:</b> None required                                                     |
|           |          |                                                    |                                                                                 |                                                                                                                          | <b>Post:</b> Can be mitigated by the planned<br>RASS for the Hand Hills WAGFs |
|           | 2017 WP  | Loss of the<br>240 kV<br>transmission<br>line 9L29 | Thermal<br>criteria<br>violation on the<br>144 kV<br>transmission<br>line 7L159 | No material<br>change                                                                                                    | <b>Pre:</b> Can be mitigated by the planned<br>RASS for the Hand Hills WAGFs  |
|           |          |                                                    | Thermal<br>criteria<br>violation on the<br>144 kV<br>transmission<br>line 7L128 | No change                                                                                                                | <b>Post:</b> Same as pre-Project                                              |
|           |          |                                                    |                                                                                 |                                                                                                                          | <b>Pre:</b> Can be mitigated by the planned<br>RASS for the Hand Hills WAGFs  |
|           |          |                                                    | Thermal<br>criteria<br>violation on the<br>144 kV<br>transmission<br>line 7L16  | No material<br>change                                                                                                    | <b>Post:</b> Same as pre-Project                                              |
|           |          |                                                    | Thermal<br>criteria<br>violation on the<br>144 kV<br>transmission<br>line 7L85  | No material<br>change                                                                                                    | <b>Pre:</b> Can be mitigated by the planned<br>RASS for the Hand Hills WAGFs  |
|           |          |                                                    | No issues                                                                       | New marginal<br>thermal<br>criteria<br>violation on a<br>240/144 kV<br>transformer at<br>the Nevis<br>766S<br>substation | <b>Post:</b> Same as pre-Project                                              |
|           |          |                                                    |                                                                                 |                                                                                                                          | <b>Pre:</b> None required                                                     |
|           |          |                                                    |                                                                                 |                                                                                                                          | <b>Post:</b> Can be mitigated by the planned<br>RASS for the Hand Hills WAGFs |

| Condition | Scenario | Results                                   |                                                                                    |                                                                              | Mitigation Measures<br>(Pre- and Post-Project)                                                                              |
|-----------|----------|-------------------------------------------|------------------------------------------------------------------------------------|------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------|
|           |          | Contingency                               | Pre-Project Observations                                                           | Post-Project Comparison                                                      |                                                                                                                             |
|           |          | Loss of the 240 kV transmission line 9L20 | Thermal criteria violation on the 144 kV transmission line 7L159                   | Materially increased thermal loading on transmission line 7L159              | <b>Pre:</b> Can be mitigated with completion of line restoration work <sup>8</sup> (Restoration) at transmission line 7L159 |
|           |          |                                           |                                                                                    |                                                                              | <b>Post:</b> Same as pre-Project                                                                                            |
|           |          |                                           | No issues                                                                          | New material thermal criteria violation on the 144 kV transmission line 7L16 | <b>Pre:</b> None required                                                                                                   |
|           |          |                                           |                                                                                    |                                                                              | <b>Post:</b> Can be mitigated with Restoration of transmission line 7L16                                                    |
|           |          | Loss of 138 kV transmission line 666L     | Voltage range criteria violation on the 138 kV bus at the Suffield 895S substation | No material change                                                           | <b>Pre:</b> Currently being mitigated using the Tilley 498S RAS                                                             |
|           |          |                                           |                                                                                    |                                                                              | <b>Post:</b> Same as pre-Project                                                                                            |
|           |          |                                           | Voltage range criteria violation on the 138 kV bus at the Tilley 498S substation   | No change                                                                    | <b>Pre:</b> Currently being mitigated using the Tilley 498S RAS                                                             |
|           |          |                                           |                                                                                    |                                                                              | <b>Post:</b> Same as pre-Project                                                                                            |

Based on the study results, Alternative 3 is technically viable. As shown in Table 8-1, the connection assessment identified a number of pre-Project and post-Project system performance issues. Real time operational practices and existing and planned RASs can be used to mitigate most of the pre- and post-Project system performance issues. Mitigation of the observed thermal criteria violations on the 144 kV transmission lines 7L159 and 7L16 following the 9L20 contingency is dependent on the restoration of the 144 kV transmission lines' respective seasonal continuous thermal ratings (as discussed in Section 7). The AESO plans to direct the TFO in the area to restore the seasonal continuous thermal ratings for transmission lines 7L159 and 7L16.

The Project does not impact the effectiveness of existing RASs in the study area, nor does the Project create the need for new RASs in the study area.

## Recommendation


<sup>8</sup> As discussed in Section 7 of this report, a number of 144 kV transmission lines in the Project area are known to be limited by current transformer (CT). The AESO plans to direct the TFO in the Project area to restore the seasonal ratings for all of these transmission lines to their normal continuous seasonal thermal ratings.

It is recommended to proceed with the Project using Alternative 3 as the preferred option to respond to the market participant's request for system access service, and to use the mitigation measures shown in Table 8-1 to manage the identified system performance issues. A minimum rating of 333 MVA is recommended for the new 240 kV circuit and is consistent with good electric industry practice as it would accommodate a possible future expansion of the Facility (for a maximum capability of up to 300 MW). The dependencies identified in this report (i.e., restoration of the seasonal continuous thermal ratings of the 144 kV transmission lines 7L16 and 7L159) need to be in service prior to energization of the Project.


**ATTACHMENT A**  
2017SL Pre-Connection Power Flow Analysis

**Table A-1: Summary of 2017SL Pre-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation    | File Name                   |
|-----|------------------|--------|-----------------|------------------|-----------------------------|
| B0  | N-0              | -      | -               | -                | 2017SL Pre-Connection (N-0) |
| B01 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S | Contingency: 9L29(N-1)      |







| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 852.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 0.0 MW   |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 502.8 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 93.5 MW  |
| Battle River #4     |  | 96.7 MW  |
| Battle River #5     |  | 279.5 MW |
| Sheerness 1         |  | 147.0 MW |
| Sheerness 29        |  | 146.0 MW |

BC Import: 25.1 MW  
 SK Import: 0.0 MW  
 MATL Import: 0.0 MW  
 Med-Hat Import: 101.6 MW  
 SOK: 426.6 MW + 0.35 x -238.2 MW

PROJECT 1533, 2017SL PRE-CONNECTION  
 CONTINGENCY: B01-9L29(N-1)  
 TUE, SEP 23 2014 8:43  
 Bus - Voltage (kV/pu)  
 Branch - MW/Mvar  
 Equipment - MW/Mvar  
 100.0%Rate A  
 1.200OV 0.900UV  
 kv: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

**AESO**

## **ATTACHMENT B**

### **2017SL Post-Connection Power Flow Analysis**


**Table B-1: Summery of 2017SL Post-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation    | File Name                    |
|-----|------------------|--------|-----------------|------------------|------------------------------|
| B0  | N-0              | -      | -               | -                | 2017SL Post-Connection (N-0) |
| B01 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S | Contingency: 9L29(N-1)       |



Bus - Voltage (kV/pu)  
Branch - MW/Mvar  
Equipment - MW/Mvar  
100.0%Rate A  
1.200OV 0.900UV  
kV: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

# AESO




| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 852.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 121.9 MW |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 624.7 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 93.5 MW  |
| Battle River #4     |  | 96.7 MW  |
| Battle River #5     |  | 279.5 MW |
| Sheerness 1         |  | 147.0 MW |
| Sheerness 29        |  | 146.0 MW |

**ATTACHMENT C**  
2017SP Pre-Connection Power Flow Analysis

**Table C-1: Summary of 2017SP Pre-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation      | File Name                   |
|-----|------------------|--------|-----------------|--------------------|-----------------------------|
| B0  | N-0              | -      | -               | -                  | 2017SP Pre-Connection (N-0) |
| B01 | N-1              | 666L   | Tilley 498S     | West Brooks 28S    | Contingency: 666L (N-1)     |
| B02 | N-1              | 669L   | Cypress 562S    | Amoco Empress 163S | Contingency: 669L (N-1)     |
| B03 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S   | Contingency: 9L29 (N-1)     |



BC Import: 551.9 MW  
SK Import: 150.0 MW  
MATL Import: 300.0 MW  
Med-Hat Import: -26.6 MW  
SOK: 219.0 MW + 0.35 x -201.2 MW


PROJECT 1533, 2017SP PRE-CONNECTION  
BASE CASE (N-0)  
TUE, SEP 23 2014 10:14

Bus - Voltage (kV/pu)  
Branch - MW/Mvar  
Equipment - MW/Mvar  
100.0%Rate A  
1.200OV 0.900UV  
kv: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

AESO








| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 854.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 0.0 MW   |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 502.4 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 123.9 MW |
| Battle River #4     |  | 126.7 MW |
| Battle River #5     |  | 300.0 MW |
| Sheerness 1         |  | 208.0 MW |
| Sheerness 29        |  | 209.0 MW |

BC Import: 552.2 MW  
 SK Import: 150.0 MW  
 MATL Import: 300.0 MW  
 Med-Hat Import: -26.6 MW  
 SOK: 219.0 MW + 0.35 x -201.0 MW

PROJECT 1533, 2017SP PRE-CONNECTION  
 CONTINGENCY: B02-669L(N-1)  
 TUE, SEP 23 2014 10:14  
  
 Bus - Voltage (kV/pu)  
 Branch - MW/Mvar  
 Equipment - MW/Mvar  
 100.0%Rate A  
 1.200OV 0.900UV  
 kv: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

**AESO**



| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 854.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 0.0 MW   |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 502.4 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 123.9 MW |
| Battle River #4     |  | 126.7 MW |
| Battle River #5     |  | 300.0 MW |
| Sheerness 1         |  | 208.0 MW |
| Sheerness 29        |  | 209.0 MW |

BC Import: 586.6 MW  
 SK Import: 150.0 MW  
 MATL Import: 300.0 MW  
 Med-Hat Import: -26.6 MW  
 SOK: 217.0 MW + 0.35 x -212.4 MW


PROJECT 1533, 2017SP PRE-CONNECTION  
 CONTINGENCY: B03-9L29(N-1)  
 TUE, SEP 23 2014 10:14  
  
 Bus - Voltage (kV/pu)  
 Branch - MW/Mvar  
 Equipment - MW/Mvar  
 100.0%Rate A  
 1.200OV 0.900UV  
 kv: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

AESO

**ATTACHMENT D**  
2017SP Post-Connection Power Flow Analysis

**Table D-1: Summary of 2017SP Post-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation    | File Name                    |
|-----|------------------|--------|-----------------|------------------|------------------------------|
| B0  | N-0              | -      | -               | -                | 2017SP Post-Connection (N-0) |
| B01 | N-1              | 666L   | Tilley 498S     | West Brooks 28S  | Contingency: 666L (N-1)      |
| B02 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S | Contingency: 9L29 (N-1)      |



| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 854.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 121.9 MW |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 624.3 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 123.9 MW |
| Battle River #4     |  | 126.7 MW |
| Battle River #5     |  | 300.0 MW |
| Sheerness 1         |  | 208.0 MW |
| Sheerness 29        |  | 209.0 MW |


BC Import: 549.2 MW  
 SK Import: 150.0 MW  
 MATL Import: 300.0 MW  
 Med-Hat Import: -26.6 MW  
 SOK: 123.2 MW + 0.35 x -228.8 MW

PROJECT 1533, 2017SP POST-CONNECTION  
 BASE CASE (N-0)  
 TUE, SEP 23 2014 9:10

Bus - Voltage (kV/pu)  
 Branch - MW/Mvar  
 Equipment - MW/Mvar  
 100.0%Rate A  
 1.200OV 0.900UV  
 kv: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

AESO









**ATTACHMENT E**  
2017WP Pre-Connection Power Flow Analysis


**Table E-1: Summary of 2017WP Pre-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation    | File Name                   |
|-----|------------------|--------|-----------------|------------------|-----------------------------|
| B0  | N-0              | -      | -               | -                | 2017WP Pre-Connection (N-0) |
| B01 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S | Contingency: 9L29 (N-1)     |
| B02 | N-1              | 9L20   | Nevis 766S      | Cordel 755S      | Contingency: 9L20 (N-1)     |



Bus - Voltage (kV/pu)  
Branch - MW/Mvar  
Equipment - MW/Mvar  
100.0%Rate B  
1.200OV 0.900UV  
kV: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000

# AESO







**ATTACHMENT F**  
2017WP Post-Connection Power Flow Analysis

**Table F-1: Summary of 2017WP Post-Connection Power Flow Analysis**

| #   | System Condition | Outage | From Substation | To Substation    | File Name                    |
|-----|------------------|--------|-----------------|------------------|------------------------------|
| B0  | N-0              | -      | -               | -                | 2017WP Post-Connection (N-0) |
| B01 | N-1              | 9L20   | Nevis 766S      | Cordel 755S      | Contingency: 9L20 (N-1)      |
| B02 | N-1              | 9L29   | Oakland 946S    | Coyote Lake 963S | Contingency: 9L29 (N-1)      |








| Existing South WAGF |  | MW       |
|---------------------|--|----------|
| WAGF Total          |  | 852.3 MW |
| Future South WAGF   |  | MW       |
| P1533 Jenner        |  | 121.9 MW |
| P479 - Wild Rose    |  | 204.0 MW |
| P635 - Suncor       |  | 81.6 MW  |
| P678 - BlueEarth    |  | 78.2 MW  |
| WAGF Total          |  | 624.7 MW |
| Coal Generation     |  | MW       |
| Battle River #1     |  | 0.0 MW   |
| Battle River #2     |  | 0.0 MW   |
| Battle River #3     |  | 151.3 MW |
| Battle River #4     |  | 154.5 MW |
| Battle River #5     |  | 376.1 MW |
| Sheerness 1         |  | 324.0 MW |
| Sheerness 29        |  | 325.4 MW |

BC Import: 568.3 MW  
SK Import: 150.0 MW  
MATL Import: 300.0 MW  
Med-Hat Import: -28.9 MW  
SOK: 396.2 MW + 0.35 x -83.6 MW

PROJECT 1533, 2017WP POST-CONNECTION  
CONTINGENCY: B01-9L20(N-1)  
TUE, SEP 23 2014 10:47

Bus - Voltage (kV/pu)  
Branch - MW/Mvar  
Equipment - MW/Mvar  
100.0%Rate S  
1.200OV 0.900UV  
kV: >0.000 <=25.000 <=69.000 <=138.000 <=240.000 <=500.000


AESO




**ATTACHMENT G**  
2017SL Post-Connection Transient Stability  
Analysis




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 17:23  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 17:23  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTATION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTATION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 17:23  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 17:23  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 17:23  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out




WED, OCT 22 2014 17:23  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 17:23  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 17:23  
MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out


WED, OCT 22 2014 17:23  
MACHINE VOLTAGE WIND PU








TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 17:23  
BRANCH REACTIVE POWER MVR




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 17:23  
BRANCH ACTIVE POWER MW




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out




THU, OCT 23 2014 11:19  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
BRANCH REACTIVE POWER MVR




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
BRANCH ACTIVE POWER MW




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:19  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:19  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:19  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out







TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out









TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 17:23  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 17:23  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 17:23  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 17:23  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 17:23  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out




WED, OCT 22 2014 17:23  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 17:23  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 17:23  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 17:23  
MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out


WED, OCT 22 2014 17:23  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 17:23  
BRANCH REACTIVE POWER MVR




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 17:23  
BRANCH ACTIVE POWER MW







TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 17:24  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 17:24  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 17:24  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 17:24  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out








TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 17:24  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 17:24  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 17:24  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out




WED, OCT 22 2014 17:24  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 17:24  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 17:24  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 17:24  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 17:24  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



**ATTACHMENT H**  
2017SP Post-Connection Transient Stability  
Analysis




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



MOTOR ANGLE (DEGREES)  
WED, OCT 22 2014 18:02




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



MACHINE POWER WIND PU  
WED, OCT 22 2014 18:02




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



MACHINE ANGLE (DEGREES)  
WED, OCT 22 2014 18:02



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




MACHINE POWER COAL PU  
WED, OCT 22 2014 18:02



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:02


MACHINE VOLTAGE COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:02


MOTOR VOLTAGE PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:02


MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out


WED, OCT 22 2014 18:02

MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:02  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:02  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:02  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:02  
MACHINE POWER COAL PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:02


MACHINE VOLTAGE COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:02


MOTOR VOLTAGE PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:02


MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out


WED, OCT 22 2014 18:02

MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out




THU, OCT 23 2014 11:19  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:19  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
BRANCH REACTIVE POWER MVR




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:19  
BRANCH ACTIVE POWER MW




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out



THU, OCT 23 2014 11:19  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:19  
MACHINE VOLTAGE WIND PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out








TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:02  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:02  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:02  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




WED, OCT 22 2014 18:02  
MACHINE POWER COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:02


MACHINE VOLTAGE COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:02


MOTOR VOLTAGE PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:02


MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out


WED, OCT 22 2014 18:02

MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:02  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:02  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:02  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out




WED, OCT 22 2014 18:02  
MACHINE POWER COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:02


MACHINE VOLTAGE COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:02


MOTOR VOLTAGE PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:02


MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out


WED, OCT 22 2014 18:02

MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out







TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:02  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:02  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:02  
MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out


WED, OCT 22 2014 18:02  
MACHINE VOLTAGE WIND PU








TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out







TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:03


MACHINE VOLTAGE COAL PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:03


MOTOR VOLTAGE PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:03


MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out


WED, OCT 22 2014 18:03

MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



**ATTACHMENT I**  
2017WP Post-Connection Transient Stability  
Analysis




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



WED, OCT 22 2014 18:51  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



WED, OCT 22 2014 18:51  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



WED, OCT 22 2014 18:51  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




WED, OCT 22 2014 18:51  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:51  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:51  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:51  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out

WED, OCT 22 2014 18:51  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTATION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out



WED, OCT 22 2014 18:51  
BRANCH REACTIVE POWER MVR



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT WAREJUNCTION SUBSTATION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 6.5 CYCLES  
FILE: 944L\_Ware.out




WED, OCT 22 2014 18:51  
BRANCH ACTIVE POWER MW






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:51  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:51  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out



WED, OCT 22 2014 18:51  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out




WED, OCT 22 2014 18:51  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:51  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:51  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:51  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTAION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out

WED, OCT 22 2014 18:51  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out





TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 944L AT JENNER SUBSTATION  
CLEARED IN 5.25 CYCLES, FAR END CLEARED IN 5.75 CYCLES  
FILE: 944L\_Jenner.out







TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:38  
MOTOR ANGLE (DEGREES)





TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:38  
MACHINE POWER WIND PU





TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:38  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out




THU, OCT 23 2014 11:38  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:38  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:38  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:38  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out

THU, OCT 23 2014 11:38  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out



THU, OCT 23 2014 11:39  
BRANCH REACTIVE POWER MVR




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT JENNER SUBSTAION  
CLEARED IN 10.5 CYCLES, FAR END CLEARED IN 5 CYCLES  
FILE: 945L\_Jennr.out




THU, OCT 23 2014 11:39  
BRANCH ACTIVE POWER MW




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:39  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:39  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:39  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




THU, OCT 23 2014 11:39  
MACHINE POWER COAL PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:39  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:39  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out

THU, OCT 23 2014 11:39  
MOTOR POWER PU



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out


THU, OCT 23 2014 11:39  
MACHINE VOLTAGE WIND PU








TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 945L AT CYPRESS SUBSTAION  
CLEARED IN 4 CYCLES, FAR END CLEARED IN 11.5 CYCLES  
FILE: 945L\_Cypress.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:52  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:52  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out



WED, OCT 22 2014 18:52  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




WED, OCT 22 2014 18:52  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:52  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:52  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTATION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT ANDERSON SUBSTATION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_And.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:52  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:52  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out



WED, OCT 22 2014 18:51  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out




WED, OCT 22 2014 18:52  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:52  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:52  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 9L50 AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 6 CYCLES  
FILE: 9L50\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out



WED, OCT 22 2014 18:52  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out



WED, OCT 22 2014 18:52  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out



WED, OCT 22 2014 18:52  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




WED, OCT 22 2014 18:52  
MACHINE POWER COAL PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:52  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:52  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT WAREJUNCTION SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_Ware.out






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 18:52  
MOTOR ANGLE (DEGREES)




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 18:52  
MACHINE POWER WIND PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 18:52  
MACHINE ANGLE (DEGREES)



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out




WED, OCT 22 2014 18:52  
MACHINE POWER COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE COAL PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:52  
MOTOR VOLTAGE PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:52  
MOTOR POWER PU




TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LT0U-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTAION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out

WED, OCT 22 2014 18:52  
MACHINE VOLTAGE WIND PU






TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTATION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 18:52  
BRANCH REACTIVE POWER MVR



TASMO MODEL; OUTPUT GENERATED 2012-11-20 09:24:15  
SWINGBUS 1520 FOR 2012LTOU-1:2015-05-24:16:12--1-0-0-0  
3 PHASE FAULT ON 240 KV 1053L AT CASSILS SUBSTATION  
CLEARED IN 5 CYCLES, FAR END CLEARED IN 7 CYCLES  
FILE: 1053L\_CASS.out



WED, OCT 22 2014 18:52  
BRANCH ACTIVE POWER MW